



موبایل: ۹۳۷۰۰۲۸۸۲۳۲

ايميل: dacaar@dacaar.org

وبسایت: www.dacaar.org

Main Office Golayee Wazirabad PO Box 208 Kabul, Afghanistan Phone: +93 202230752 Mobile: +93 700288232 E-mail: dacaar@dacaar.org

Website: www.dacaar.org

REQUEST FOR QUOTATION

Drilling of One Tube Well by Mud Rotary Rig in Bahadur Khil Village Saved Abad District of Maidan Wardak Province

درخواست آفر برای حفر یک حلقه چاه آب آشامیدنی توسط ماشین سیستم دورانی در قریه بهادرخیل ولسوالی سیدآباد ولایت میدان وردک

Date: June 13, 2024

individuals for Drilling of One Tube Well by Mud و یمپ تست را در قریه بهادرخیل ولسوالی سیدآباد ولایت میدان Rotary Drilling Rig with Compressor and Pump Tests in وردک داشته باشند دعوت بعمل میآورد تا در پروسه داوطلبی Bahadur Khil Village Saved Abad District of Maidan Wardak Province.

Please use Annex (I) Budget Breakdown for submitting your offers, price must include Government Tax. Please Use Annex (II), for Tentative Work Plan.

The offers must reach to DACAAR Main Office Logistics Unit located in Street No. 12, Taimani Project, Qala-e-Fathullah - Kabul Province till 4:00pm June 24, 2024.

The bid opening session will be held on June 25, 2024 at 10:00am in DACAAR Main Office, Kabul Province, and the bid winner will be notified shortly after the bid opening session.

Terms and Conditions for the bid winner/participants

- 1. Price must be in Afghani including 2% Tax for the registered companies (Drilling Activity) and 7% Tax for unregistered companies or expired licensed companies. Tax will be applicable over (1AFN). Please attach copy of your license with your offers.
- 2. The bid winner should deposit (100,000 AFN) as a Contract Performance Guarantee and submit the deposit slip to DACAAR Logistics Unit.

Work Specifications:

- 1. The well should be drilled by mug rotary rig with 14-inch diameter drilling bit from the surface to the depth of 100m. The Depth of well will be increased or decreased in case of geological condition but, the final decision will be taken by DACAAR Hydrogeology/ Technical Staff.
- 2. The well from the starting to the ending of drilling should not be less than 14 inches drilling bit.

DACAAR RFO 57 PRF-390/ECHO/2401-ECHO/EHWR1.3.9/WRD-0407/06.2024 داکار از همه شرکت ها و اشخاص انفرادی که علاقمندی حفر یک Sealed offers are invited from qualified companies and حلقه جاه آب آشامیدنی توسط ماشین سیستم دو ر انی معه کمبریسو ر اشتر اک نمایند

> لطفاً برای ارائه آفر لست ضمیمه (I) را استفاده نمائید و قیمت ها باید شامل مالیه دولت باشد. بلان تخمینی کار در است ضمیمه (۱۱) گذاشته شده است

> آفرها بايد الى تاريخ 24 جون 2024 ساعت 4:00 عصر به شعبه لوجستیک دفتر مرکزی داکار واقع بروژه تایمنی پایکوب نصوار سرك 12 قلعه فتح الله و لايت كابل سير ده شود.

> آفرگشایی ساعت 10:00 قبل از ظهر تاریخ 25 جون 2024 در دفتر مرکزی داکار واقع ولایت کابل صورت میگیرد که متعاقباً برنده داوطلبي در اسرع وقت اطلاع خواهد يافت.

شرایط قرارداد برای برنده داوطلبی/ اشتراک کننده گان

- 1. قیمت ها به افغانی داده شو د و باید شامل %2 مالیه دولت برای کمینی هائیکه دارای جواز (فعالیت حفاری) میباشند و %7 مالیه برای کمپنی هائیکه دارای جواز دولتی نمیباشند ویا معیاد معینه تمام باشد، از (1 افغانی) به بالا مالیه وضع میگردد. لطفاً جواز كارى را شامل آفر تان نمايد.
- 2. برنده قرارداد باید (100,000) افغانی را جهت تضمین اجرا قراداد بحساب بانکی داکار واریز نمایند و سند پرداخت انرا به بخش تدار کات داکار ارایه نمایند.

جزئيات و مشخصات كار:

- 1. حفاري جاه توسط ماشين دوراني صورت گيرد که از سطح زمين به عمق 100 متر به قطر بل برمه 14 انچ حفاري گردد. عمق چاه نظر به شرایط جیولوجکی میتواند کمتر ویا بیشتر شود ولى تصميم نهايي از طرف هايدروجيولوج/ كارمند تخنیکی داکار اتخاد میگردد.
- 2. قطر چاه از شروع برمه كارى الى ختم برمه كارى نبايد كمتر از 14 انچ باشد (14 انچ مطابق بل برمه).

- 3. قطر راد هاى برمه بايد بين 89 الى 100 ملى متر باشد.
- 4. The contractor should have heavy rod and should be used between drilling rod and drilling bit. The heavy rod should not be less than 1500 Kg.

3. Drilling Rod diameter should be 89 or 100mm.

5. The drilling bit should be according to the well litho logical layers. Secondly the drilling bit must be completely stable and free from breakage, looseness

and abrasion.

- 6. The contractor will be responsible of lowering and installation of screen and pipe in a straight line in the well.
- 7. The contractor should take the sample from each meter and put in to the sample box and label of each sample intervals. The contractor must have the sample box.
- 8. The contractor should have the water tanker for circulation of water to the well during drilling and cleaning of well during gravel packing. The water tanker capacity should not be less than 15 cubic meters.
- 9. The contractor must lower PVC 8-inch Casing Pipe and Filter Class E according to the well design (cost per meter). DACAAR will provide 8 inches PVC pipe and screen according to the well design.
- 10. Around the pipe and screen should be filled by impervious clay and 2-6mm rounded, sorted and washed river gravel according to the well design cost per meter. Backfilling and provision of its materials are the responsibility of the contractor (the sorted and washed river gravel must be provided by the contractor).
- 11. Around the pipe, above the water level should be filled with impervious clay according to the well design (Cost per meter). The impervious clay is prepared by the contractor the impermeable clay should be pure clay or Bentonite and should not contain any metallic or non-metallic compounds and organic material. The location of impermeable mud is determined by DACAAR field engineer
- 12. The contractor should be entitled for the cost per meter of gravel pack and the impervious clay seal.
- 13. <u>Compressor Test:</u> The well should be cleaned and developed by air Compressor with three inches GI outlet pipe (with joint of Flange) and one inches GI air pipe or PE pipe 32mm (10 Bar- PE 80) (one job) until the water of well completely cleaned from mud, silt and dust. The capacity of compressor Page 2 of 9

- 4. قرارداد گیرنده مکلف به داشتن راد سنگین باشد و از آن در اثنای برمه کاری در بین رادهای برمه و پل برمه کاری استفاده نماید، راد سنگین باید از 1500 کیلو گرام کم نباشد.
- پل برمه باید مطابق طبقات احجار چاه باشد. و همچنان الاشه های پل برمه باید مستحکم و عاری از شکستگی، لقی و سابید گی باشد.
- 6. قرارداد گیرنده مکلف به نصب و پایین نمودن نل و فلتر بطور مستقیم در چاه میباشد.
- 7. قرارداد گیرنده مکلف به اخذ نمونه از هر متر حفاری بوده و بعد از اخذ نمونه آنرا در بکس نمونه گیری جابجا نماید و متراج هر نمونه را برجسپ نماید. داشتن بکس نمونه گیری حتمی میباشد.
- 8. قرارداد گیرنده مکلف به داشتن تانکر آب بوده که در جریان حفاری و پاک کاری با جریان دادن آب در داخل چاه از آن استفاده میشود. ظرفیت تانکر آب باید از 15 متر مکعب کمتر نباشد.
- 9. قرارداد گیرنده مکلف به پایین نمودن نل و فلتر 8 انچ کلاس
 E مطابق به دیزاین چاه میباشد (قیمت پایین نمودن نل و فلتر در چاه به فی متر)، و تهیه نل و فلتر مسولیت داکار میباشد.
- 10. اطراف پایپ و فاتر توسط جغل دریایی سورت شده, اشم و شسته شده به سایز 2 الی 6 ملی متر مطابق به دیزاین چاه پر کاری گردد. پرکاری اطراف پایپ و تهیه مواد مورد نیاز از جمله مسؤلیت های قرارداد گیرنده میباشد. (جغل دریایی سورت شده از طرف قرارداد گیرنده تهیه میگردد).
- 11. قسمت اطراف نل که بالاتر از سطح آب قرار دارد توسط گل غیر قابل نفوذ مطابق به دیزاین چاه پرکاری گردد (قیمت فی متر). گل غیر قابل نفوذ از طرف قرارداد گیرنده تهیه میگردد گل نفوذ ناپذیر باید بنتونیت یا خاک رس خالص باشد و حاوی هیچگونه ترکیب فلزی، غیر فلزی ومواد عضوی نباشد موقعیت قرارگیری گل غیری قابل نفوذ از طرف انجینر ساحه معین می شود.
- 12. قرارداد گیرنده تنها مستحق پول پرکاری فی متر جغل دریایی و فی متر گل غیرقابل نفوذ اطراف نل و فاتر درچاه میباشد.
- 12. ياک کارى و انکشاف چاه ها توسط ماشين کمپريسور 12 اتمسفير فشار هوا که داراى نل 8 انچ جستى پر تاب آب (با اتصالات پلنج 8 انچ) و نل هواى جستى 1 انچ ويا پى اى پايپ 32 ملى متر 1 ابر 18 (PE 19 الى پاک

should be 12 atmospheres (output of pressure) and should be able to clean and develop the well to the depth of maximum 100m. The development of well means to close and open the gate valve of water pipe outlet during compressor operation for better cleaning and sorting of gravel and sand around the pipe and screen.

14. <u>Pumping Test</u> should be performed by electric submersible pump minimum for 8 hours for finding well hydraulic properties, such as static water level, discharge, dynamic (water level) time draw downed time recovery. If the Tube Well produces less than 5 L/s, the contractor should provide electrical submersible pump according to the mentioned Tube Well discharge for pumping test.

The minimum and maximum discharge of pump should be between 5-7 L/s and the pump head should not be less than 100m. The power of generator should be according to the power of water pump and to have stable power during pumping test.

The contractor should have water level indicator, valve and flow meter for control of well discharge during pumping test of well.

- 15. The contractor should arrange for Helmet, Safety Shoes, Safety Glass and Leather Glove for Safety of his working team.
- 16. The contractor should provide hard and soft copies of report for well construction and pumping test

Note: Before of lowering casing, screen and gravel packing the Contractors should provide all required materials/equipment, such as, compressor machine, pumping test equipment, Generator, water tanker and etc. at site.

CONTRACTOR'S RESPONSIBILITIES:

- 1. Start and completion dates for contract shall be according to work plan in Annex II.
- Contractor is responsible for logistics cost during shifting / transportation of equipment to the project area.
- 3. Any breakdown or other delays must be reported to DACAAR as soon as possible.
- 4. Where the water table is less than 5 meters then the well should be sealed by impermeable clay to prevent water reaching the top and upper parts of the well.

شدن آب از ریگ میده، گل و لای صورت گیرد. هدف از انکشاف چاه عبارت از باز و بسته کردن کیت وال پایپ آب در هنگام پاک کاری چاه برای سورت شدن جغل در اطراف نل و فلتر میباشد و این عملیه الی عمق اعظمی 100 متری صورت گیرد.

14. یمپ تست چاه باید توسط پمپ برقی حد اقل به مدت 8 ساعت برای دریافت پارامترهای هایدرولیکی چاه مانند سطح استاتیکی آب، ظرفیت آبدهی، سطح دینامیکی، زمان نشست و احیا دوباره آب چاه انجام شود، در صورتیکه چاه کمتر از 5 لیتر آب در فی ثانیه تولید کند، در آنصورت قرارداد گیرنده مکلف است تا واتر پمپ برقی زیر آبی مطابق به تولید مقدار آب جاه بخاطر بمب تست تهیه نماید.

اخراج اعظمی و اصغری پمپ باید بین 5 تا 7 لیتر درثانیه باشد و قدرت پرتاب پمپ نه باید کمتر از 100 متر باشد. قدرت جنراتور برق باید مطابق توان پمپ برقی باشد که بتواند به مدت زمان معین شده خاموش نشود.

قرارداد گیرنده در جریان پمپ تست باید نشانگر سطح آب (فیته برقی اندازه گیری آب)، وال همرا با جریان سنج (فلومتر) برای کنترل و اندازه گیری تخلیه آب چاه داشته باشد.

- 15. قرارداد گیرنده جهت مصوونیت پرسونل برمه کاری در جریان کار مکلف به تهیه کلاه محافظوی، بوت، لباس، عینک و دستکش چرمی در ساحه میباشد.
- 16. قرارداد گیرنده باید راپور ساختمان و پمپ تست چاه را هم در سافت و هم در هارد تهیه نماید.

نوت: قبل از نصب نل، فلتر و جغل قرادادی باید همه تجهیزات پمپ تست و کمپریسورکاری را از قبیل (کمپریسور، و اتریمپ، جنراتور، تانکر آب و جریان سنج) را آماده کند.

مسئولیت های قرارداد گیرنده:

- 1. تاریخ ختم و شروع کار مطابق پلان کاری که در است ضمیمه (II) ذکر گردیده، قرارداد گیرنده مکلف به اجرا آن مبیاشد.
- 2. مسئولیت انتقال، نصب سامان آلات حفاری مربوط خود قرارداد گیرنده میباشد و داکار هیچگونه مسئولیت لوجستکی و یا اداری در برابر قرارداد گیرنده را در جریان اجرأ قرارداد ندارد.
- هیچگونه تأخیر و یا توقف کاری در جریان اجرا قرارداد مجاز نیست و در صورت بروز مشکل باید فوراً داکار در جریان گذاشته شود.
- 4. در جاهائیکه سطح آب کمتر از پنج متر باشد، قرارداد گیرنده مکلف است تا بمنظور جلوگیری از عبور آب در قسمت های فوقانی چاه ، آب چاه را توسط گل غیر قابل نفوذ آب بسته نماید.
- 5. قر ارداد گرنده مكلف و مؤظف به تهيه ريگ و حغل 6-2

- 5. The Contractor should use river washed sand sorted gravel (2-6mm) for filling around filter Gravel shall be composed of clean, round, hard, water-worn siliceous material, free of flat or elongated pieces, organic matter, or other foreign matter. Contractor is responsible for impermeable material for backfilling of around casing but still confirmation of the field officer is necessary on amount of back filling for screen and casings, it should be noted that, the cost of Gravel packing is separate, and cost of impermeable materials is separate.
- 6. The Contractor will be fully responsible for vertical straight bore holes.
- 7. If the drilled well provide turbid unsafe water, that is the responsibility of contractor to rectify the problem. Otherwise DACAAR will not pay for well providing turbid water.
- 8. The contractor does not have the right to make contract with another party.
- 9. During the back filling, using of heavy machine is prohibited, only shovel should be used.
- 10. The contractor must regularly check the electrical conductivity of water in absence of field engineer, when the driller faces with saline layer of water the contractor should immediately stop the drilling process and inform the field Engineer-in-Charge
- 11. The contractor must be able to block the saline layer and have the experience of blocking. And also The supplier should have engineer or technical staff to support their drilling process.
- 12. The contractor should not use other blocking materials such as cement, gypsum, etc. during drilling process except for drilling mud (Clay).

DACAAR RESPONSIBILITIES:

- Timely supply of materials from DACAAR field office to the project: materials include 8-inch diameter PVC Pipes and Filter for lining of the well.
- DACAAR's monitoring and water testing representative to be at the site to check the depth of the well to assist the static water level and ensure enough of water column and to test the approximate quality and taste of water.

ملی سورت شده مناسب ریگ شسته شده دریایی جهت پرکاری اطراف پایپ فلترها میباشد جغل باید مرکب از مواد سلیسی،گرد، سخت، انتقال یافته توسط آب باشد قطعه و پارچه طولی ، پهن،هموار، مواد عضوی وسایر ترکیبات را نداشته باشد و باقی پایپ ها ازگل غیرقبل نفوذ برای پرکاری اطراف کیسنگ استفاده نماید، البته مقدار پرکاری در اطراف فلتر و کیسنگ توسط انجنیر ساحه تثبیت میگردد، که این تصمیم با در نظرداشت ساحه صورت میگیرد، قابل تذکر است که قیمت پرکاری توسط ریگ شسته شده دریایی جدا است و قیمت پرکاری غیر قابل نفوذ جدا است و از جمله مسؤلیت های قرارداد گیرنده میباشد.

- مسیر عمق چاه باید عمود باشد و قرارداد گیرنده مسئولیت راست بودن عمق چاه را به عهده دارد.
- 7. در صورتیکه آب چاه نا صاف و گل آلود و یا غیر آشامیدنی باشد مسئولیت قرارداد گیرنده است که آنرا تصحیح و بر طرف نماید. داکار پول چاه را که دارای آب نا صاف باشند نمی پردازد.
 - 8. قرارداد گیرنده حق ندارد که با شخصی دیگر قرارداد نماید.
- در جریان پرکاری چاه، فقط با بیل پر کاری گردد نه با ماشین های ثقیل.
- 10. قرارداد گیرنده باید در عدم موجودیت انجنیر ساحه بطور مداوم شوری آب را چک و برسی نماید، و در هنگام برخورد با لایه شور حفار پروسه برمه کاری را متوقف ساخته و موضوع را به انجنیرمسئول ساحه اطلاع دهد.
- 11. قرارداد گیرنده توانایی و تجربه قبلی را در مسدود نمودن لایه های شور داشته باشد و همچنان قرارداد گیرنده باید انجنیر یا کارکنان فنی برای پشتیبانی از فرآیند حفاری خود داشته باشد.
- 12. قرارداد گیرنده در جریان حفاری به جزاز گل حفاری (خاک کلی) و از سایر مواد مسدود کننده از قبیل سمنت، گچ و غیره در جریان برمه کاری استفاده ننماید

مسئولیت های داکار:

- 1. رساندن بر وقت مواد از دفتر ساحوی داکار به پروژه: مواد شامل یایپ و فلتر 8 انچ برای سطر کردن چاه.
- 2. نماینده داکار در بخش نظارت از جریان حفاری چاه وسمپل گیری، اندازه گیری سطح اب وتست فیزیکی کیفیت اب در ساحه حضور خواهد داشت.
- 3. موقیعت چاه فقط توسط نماینده رسمی داکار تعین میگر دد، اما

- 3. The Locations of the well will be determined by DACAAR only. In case, Contractor relocates a well without first obtaining DACAAR's written approval then DACAAR will not be liable to make any payment for the well.
- 4. Payments will be made against receipt of invoice through DACAAR Regional Office in its concerned Province after successful completion of bored well. Verification on well completion is needed from the DACAAR monitoring engineer who is responsible for the project.
- 5. In case of bad or salty water in the well, the materials for blocking of the well (cement, clay, bentonite/ and other impermeable materials, or an equivalent) will be provided by DACAAR and the cost of labour for blocking will be paid by Contractor.
- 6. The contractor must regularly check the electrical conductivity of water in absence of field engineer, when the driller faces with saline layers of water the contractor should immediately stop the drilling process and inform the field engineer.
- 7. DACAAR will pay Contractor according to fixed price in the contract.
- 8. DACAAR is not responsible for security or any damages (human or machinery) caused during implementation of contract.

Contract Terms and Conditions:

- Start and completion of drilling work shall be based on the work plan in annex (II) of this contract.
- 2. In case of delays caused by the contractor, 0.5% of remaining work will be charged as a delays penalty on each day of delay, this role is applicable till one month, after one to two month 20% penalty, delaying more than two months, will cause penalty of 30%.
- 3. Quotations should be valid for 60 working days.
- Contractor has the obligation to complete all well in specified time. Delays caused by natural disaster or geological problems are exceptional but both DACAAR and Contractor must certify and agree on the cause of delay.

- در صورتیکه قرارداد گیرنده به میل خود موقیعت چاه را تغییر میدهد و ان هم بدون هماهنگی قبلی با داکار در قسمت پرداخت پول این نوع چاه هیچگونه مسؤلیت نخواهد داشت.
- 4. پرداخت پول در مقابل رسید انوایس و بعد از ختم موافقانه چاه توسط دفتر ساحوی داکار در ولایت مربوطه قابل اجرأ میباشد که توسط نماینده با صلاحیت داکار تصدیق میگردد و در اخیر هر ماه از کامیاب بودن چاه راپور داده میشود، تصدیق چاه توسط انجنیر که مسؤل پروژه بوده چاه را بررسی مینماید ضروری است.
- 5. در صورت کیفیت پایین آب و یا شور بودن طعم آن مواد مورد ضرورت از قبیل خاک رس، بینتونیت، سمنت وسایر مواد غیر قابل نفوذ غرض بسته نمودن چاه مذکور توسط داکار تهیه خواهد گردید، و قیمت کارگری غرض بسته کردن چاه توسط قرار داد گیر نده بر داخت خواهد گردید.
- 6. قرارداد گیرنده باید در عدم موجودیت انجنیر ساحوی بطور مداوم شوری آب را چک و بررسی نماید، و در هنگام برخورد با لایه های آب شور حفار پروسه برمه کاری را متوقف ساخته و موضوع را به انجنیر ساحوی اطلاع دهد.
- 7. پرداخت اجوره حفر چاه مطابق قیمت تعین شده در قرارداد خواهد بود.
- 8. داکار مسئولیت امنیتی و یا حوادث غیر مترقبه مانند خسارات مالی و یا جانی در جریان اجراً قرار داد را عهده دار نمیباشد.

شر ابط قر ار داد:

- 1. شروع و ختم حفر چاه باید مطابق پلان کاری است ضمیمه (II) قر ار داد باشد.
- در صورت تأخیر بدون موجب از طرف قرارداد گیرنده در حفر چاه مبلغ %0.5 بطور جریمه در بدل هر روز از کار باقی مانده از قرارداد گیرنده وضع میگردد، تأخیر از یک ماه الی دو ماه %20 جریمه دارد و تأخیر بیشتر از دو ماه %30 جریمه را باعث میگردد.
- قیمت های داده شده باید به مدت 60 روز کاری مدار اعتبار باشد.
- 4. قرارداد گیرنده مکلف به تکمیل حفر چاه در زمان معینه در قرارداد میباشد. مشکلات های ناشی از حوادث غیر مترقبه طبیعی و یا مشکلات های ناشی از عدم امنیت در جریان کار پروژه شامل این بند نمیباشد اما در صورت بروز چنین حوادث باید توافق و تائید جانبین قرارداد در آن باشد.

- 5. The sites for the well will be selected by DACAAR, and the contractor has no right for selection of location for well.
- 6. Transportation cost of machineries, food and accommodation will be contractor's responsibility.
- 7. The Contractor has to take into consideration the work specification project completion period. Contractor must be able to finish the work for the signed contract; otherwise, he/she will be replaced with the new party and the call deposit/contract performance guaranty will not be refunded.
- One-week prior notice will be given for contract termination. Only work completed under specification will be paid by DACAAR and Contractor will return all unused materials given by DACAAR.
- 9. The contractor should confirm his active presence and activities during first weeks, after signing of the contract; otherwise, DACAAR will take the decision on cancellation of the contract. DACAAR representative must report the issue to DACAAR Main Office on time.
- 10. Award of Contract will be based on the capacity/potentiality. Thorough evaluation of potential/shortlisted bidder will be carried out. DACAAR reserves the right to make the decision of awarding contract.
- 11. Offers without thumb, signature or stamp will be rejected automatically and the bidders have no right to complain.
- 12. DACAAR will not be responsible for any changes occurred during the contract such as (increment in custom duties, exchange rate etc...)
- 13. DACAAR (Logistics Unit) adheres to National and International laws on child labour DACAAR makes sure all its vendors by such laws preventing child labour in all DACAAR activities countrywide.
- 14. The Humanitarian Organizations (HO) may conduct on- site visit in the contractor's premises (or may take similar measures) to ensure compliance.
- 15. DACAAR has a zero-tolerance policy on sexual exploitation, abuse and harassment, which is defined and described in the policy document "DACAAR policy on preventing and handling sexual exploitation, abuse and harassment".

- انتخاب ساحات برای حفر چاه توسط داکار صورت خواهد پذیرفت، و قرارداد گیرنده حق انتخاب را ندارد.
- 6. قیمت انتقال ماشین آلات، غذا، سرپناه مسئولیت قرار داد گیرنده میباشد.
- 7. قرارداد گیرنده مکلف به اجراً و تکمیل قرارداد در مدت تعین شده در این قرارداد میباشد و پلان ها باید مطابق آن پیش برود، در صورت عدم تطبیق برنامه ها مطابق پلان تعین شده و یا کیفیت پاین کارها، داکار حق فسخ قرارداد را دارد و پول تضمین اشتراک در داوطلبی قابل باز پرداخت نخواهد بود.
- 8. در صورت فسخ قرارداد، قرارداد گیرنده در ظرف یک هفته رسماً اطلاع خواهند یافت. فقط کارهای که مطابق مشخصات تعین شده در قرارداد میباشد قابل قبول خواهد بود و تمام مواد تهیه شده استفاده نشده توسط داکار دوباره به داکار بر گردانده خواهد شد.
- 9. قرارداد گیرنده باید در هفته نخست حضور فعال و کاری خود را در ساحه به اثبات برساند، در غیر آن صورت داکار در قسمت فسخ قرارداد و تصامیم لازمه اقدام خواهد نمود. نماینده داکار باید دفتر مرکزی را عندالموقع در جریان بگذارد.
- 10. برنده شدن قرارداد نظر به قیمت، کیفیت، توانائی و ظرفیت داوطلب بوده، و بعد از بررسی کمپنی صورت خواهد گرفت. البته داکار حق تصمیم گیری در این زمینه را دارا میباشد.
- 11. آفر بدون شصت، امضاً و یا مهر بطور اتومتیک رد گردیده و داوطلبان حق شکایت را ندارد.
- 12. داکار به هیچ عنوان مسؤولیت بلند رفتن مالیات گمرکی، قیمت اسعار خارجی وغیره موارد که باعث بلند رفتن قیمت در جریان قرارداد گردد ندارد.
- 13. دفتر داکار (شعبه لوژیستیک) با درنظرداشت قوانین ملی و بین المللی برای جلوگیری از کار کودکان مصمم بوده و سعی میکند که تمام فعالیتهای تهیه کننده گان و مشتریان این اداره به این اصل پابند باشند.
- 14. سازمان های بشر دوستانه (HO) ممکن است تا از محلات و سایت ها بخاطر اطمینان بیشتر و تطبیق درست کار توسط قرارداد گیرنده بازدید بعمل آورده ویا ممکن است اقدامات مشابه را انجام دهد.
- 15. داکار دارای پالیسی عدم تحمل در مورد سؤ استفاده، بد رفتاری و آزار و اذیت جنسی میباشد و موقف داکار در همچون مسایل بطور تفصیلی در پالیسی مذکور تشریح شده است.

For more details, please visit DACAAR Logistics Unit Main Office Kabul, Sunday through Thursday, from 8:00am to 03:00pm. Or contact on below Email Addresses: jamal@dacaar.org or wasimullah@dacaar.org

Sincerely Yours,

Manager – Logistics Unit

Date: June 13, 2024

ANNEX (I) BUDGET BREAKDOWN/فورم ارائه آفر DACAAR RFQ 57 PRF-390/ECHO/2401-ECHO/EHWR1.3.9/WRD-0407/06.2024

Drilling of One Tube Well by Mud Rotary Rig in Bahadur Khil Village Sayed Abad District Maidan Wardak Province:

			UNIT COST PER METER (AFN) PLUS 2% OR 7 % TAXES				Compressor Test	Pumping Test (One Job) (Should be performed by electric	
S/N	Districts/ Village	Total No of Well	Drilling Well by Mud Rotary Rig and using of 14" diameter bit from starting to the depth of 100m (AFN/ Per Meter) فتيمت في	Lowering of 8 inches PVC Pipe Class E and Filter Class E. (Only pipe and Filter lowering wage) (AFN/ Per Meter) في تيم متر پايين نمودن پايپ	Backfilling by impervious clay and Gravel packing by sorted and washed river gravel size (2-6 mm according the well design). The price should include costs of materials and backfilling wages. (AFN/ Per Meter)	Total Cost Per/Meter (AFN) قبمت محموعی فی متر کندنکاری، پایین نمودن پردکاری	Particles, dust and any other extra material of well,	(Should be performed by electric submersible pump minimum for 8 hours for finding well hydraulic properties, and Record such as static water level, discharge, dynamic water level and time recovery. The minimum and maximum discharge of pump should be between 5-7 L.s and the pump head should not be less than 100m. The power of generator should be according to the power of water pump and should have stable power during pumping test.	Grand Total Costs (Afghani) (Including Government Tax, Total Costs of Drilling, Lowering, Backfilling, Compressor and Pump Test)
1	Bahadur Khil Village Sayed Abad District of Maidan Wardak Province	One (100 M Depth)							

Bidder Name:	اسم آفر دهنده:
Address and Stamp:	آدرس و مهر کمپنی
Mobile No:	نمبر تماسنمبر تماس
Email Address:	ايمل آدر س

ANNEX (II) TENTATIVE WORK PLAN / پلان کاری تخمینی DACAAR RFQ 57 PRF-390/ECHO/2401-ECHO/EHWR1.3.9/WRD-0407/06.2024

Drilling of One Tube Well by Mud Rotary Rig in Bahadur Khil Village Sayed Abad District Maidan Wardak Province:

S/No	Province	Province District/Village		No of Rotary Rig Required	Start of Work	Completion of Work
1	Maidan Wardak	Bahadur Khil Village Sayed Abad District of Maidan Wardak Province	One	One	Starts Upon DACAAR Contract Final Approval	July 30, 2024