



Main Office

REQUEST FOR QUOTATION

Golayee Wazirabad PO Box 208 Drilling of 28 Tube Wells by Heavy Percussion Rig in Ghazni and Maidan Kabul, Afghanistan **Wardak Provinces** Phone: +93 202230752

Mobile: +93 700288232

درخواست آفر برای حفر 28 حلقه چاه آب آشامیدنی توسط ماشین سنگین کوبه ای E-mail: dacaar@dacaar.org در ولایات غزنی و میدان وردک Website: www.dacaar.org

موبایل: ۹۳۷۰۰۲۸۸۲۳۲+ ايميل: dacaar@dacaar.org وبسایت: www.dacaar.org

Date: June 27, 2024

DACAAR RFQ 61 PRF-414 and 415/ECHO/2401-ECHO/EHWR1.3.7/06.2024

DACAAR invites qualified interested companies/ individuals to submit their sealed offers for Drilling of 28 Tube Wells by heavy Percussion Rig in Ghazni and Maidan Wardak Provinces.

The offers must reach to DACAAR Main Office Logistics Unit located in Street No. 12, Paykobe-Naswar, Qala-e-Fathullah, Kabul till 4:00pm July 08, 2024.

The Bid Opening Session will be held on July 10, 2024 at 10:00am in DACAAR Main Office, Kabul Province and the Bid Winner will be notified shortly after the bid opening session.

Please use Annex (I) Budget Breakdown submitting your offers and Tentative Work Plan mentioned in Annex (II).

Terms and Conditions for Participants/Bid Winner

- 1. Price must be in Afghani including 2% Tax for the registered companies (Drilling Activity) and 7% Tax for unregistered companies or expired licensed companies. Tax will be applicable over (1AFN). Please attach copy of your license with your offers.
- 2. The bid winner should deposit (100,000 AFN) as a Contract Performance Guarantee and submit the deposit slip to DACAAR Logistics Unit.

داکار از همه شرکت ها و اشخاص انفرادی که علاقمندی حفار ی 28 حلقه چاه های آب آشامیدنی توسط ماشین سنگین کوبه ای را در و لایات غزنی و میدان وردک داشته باشند تقاضا بعمل میآورد تا آفر های سربسته شانرا قبل از معیاد تعین شده به دفتر مرکزی داکار بسیارند.

آفرها بايد الى تاريخ 08 جولاى 2024 ساعت 4:00 عصر به شعبه لوجستیک دفتر مرکزی داکار واقع پایکوب نصوار سرک 12 قلعه فتح الله و لايت كابل سيرده شود.

آفرگشایی ساعت 10:00 قبل از ظهر تاریخ 10 جولای 2024 در دفتر مرکزی داکار در ولایت کابل صورت میگیرد که متعاقباً برنده داو طلبي در اسرع وقت اطلاع خو اهد يافت.

لطفاً براى ارائه آفر از لست ضميمه (۱) استفاده نمائيد و بلان تخمینی کار در است ضمیمه (۱۱) گذاشته شده است.

شرایط قرارداد برای برنده داوطلبی/ اشتراک کننده گان

- قيمت ها به افغاني داده شود و بايد شامل 2% ماليه دولت برای کمینی هائیکه دارای جواز (فعالیت حفاری) میباشند و %7 مالیه برای کمپنی هائیکه دارای جواز دولتی نميباشند ويا معياد معينه تمام باشد، از (1 افغاني) به بالا مالیه وضع میگردد. لطفاً جواز کاری را شامل آفر تان نمابد
- برنده قرارداد باید (100,000) افغانی را جهت تضمین اجرا قراداد بحساب بانكى داكار واريز نمايند و سند برداخت انرا به بخش تدارکات داکار ارایه نمایند.

Details of Work Specifications:

1. The wells should be drilled by heavy percussion rig to the depth of 60 M, the size of the bucket should not be less than 10-inch diameter. The well depth may increase or decrease in case of geological condition but the final decision will be made by DACAAR field engineer with the technical consultation of Hydro geological staff in Kabul.

تفصیل تخنیکی کار ها:

حفاری چاه ها باید توسط ماشین سنگین کوبه ئی به عمق 60 متر و با قطر بوکه یکه قطر خارجی آن کمتر از 10 انچ نباشد، عمق چاه نظر به شرایط جیولوجکی میتواند کمتر ویا بیشتر شود ولی تصمیم نهایی از طرف هایدر و جیولو ج/ کار مند تخنیکی داکار اتخاد میگردد.

- 2. The contractor must have the temporary casing according to the drilling of bucket size and also have heavy bit (Jabal) (1.5 2 Ton), in case of need the contractor must use temporary casing.
- 3. The contractor should lower 4 inches' diameter uPVC pipe and filter in straight line according to the well design.
- 4. DACAAR will provide 4 inches' diameter uPVC pipe and filter according to the wells design.
- 5. Around the pipe and screen should be filled by impervious clay and 2-6mm rounded, sorted and washed river gravel according to the well design cost per meter. Backfilling and provision of its materials are the responsibility of the contractor.
- 6. Around the pipe, above the water level should be filled with impermeable clay according to the well design.
- 7. The contractor should have proper and standard sample box to take the sample from each meter and put in to the sample box.
- 8. Hard stratum cannot be reason for drilling of wells.
- 9. The contractor will be entitled for the cost per meter of gravel pack and the impervious clay seal.
- 10. The contractor should arrange for helmet, safety shows, overall, safety glass and leather glove for the safety purpose of working team.
- 11. The work should be carried out in term of the technical specification and plan which is provided by DACAAR.
- 12. The contractor must clean the area from dust and additional stones after the work completion.

- 2. قرارداد گیرنده مکلف به داشتن کیسنگ مؤقتی مطابق به سایز بوکه و داشتن راد سنگین (جبل به وزن 1.5 الی 2 تن) باشد، در صورت ضرورت قرارداد گیرنده از کیسینگ مؤقتی استفاده نماید.
- قرارداد گیرنده مکلف به پایین و نصب نمودن پایپ و فلتر یو پی وی سی 4 انچ بشکل عمود و مستقیم به داخل چاه مطابق به دیزاین چاه میباشد.
- داکار پایپ یو پی وی سی و فاتر 4 انچ را طبق دیزاین چاه تهیه مینماید.
- 5. اطراف پایپ و فاتر توسط جغل دریایی سورت ، لشم و شسته شده به سایز 2 الی 6 ملی متر و گل غیر قابل نفوذ مطابق به دیزاین چاه پرکاری گردد. پرکاری اطراف پایپ و تهیه مواد مورد نیاز از جمله مسؤلیت های قرارداد گیرنده میباشد.
- 6. اطراف پایپ بالاتر از سطح آب توسط گل غیر قابل نفوذ مطابق دیز این چاه پر کاری گردد.
- قرارداد گیرنده مکلف به داشتن سمپل باکس معیاری مطابق به عمق چاه بوده و بعد از اخذ نمونه آنرا در جبعه نمونه گیری جابجا نماید. (اخذ نمونه بعد از هر متر حفاری صورت گیرد).
 - 8. طبقات سخت مانع حفارى چاه ها شده نميتواند.
- 9. قرارداد گیرنده تنها مستحق پول پرکاری فی متر جغل دریایی و گل غیر قابل نفوذ اطراف نل و فلتر در چاه میباشد.
- 10. قرارداد گیرنده جهت مسئونیت پرسونل برمه کاری مکلف به تهیه کلاه محافظوی، بوت، لباس کار، عینک محافظوی و دست کش چرمی میباشد.
- 11. کار ها باید بر مبنای مشخصات تخنیکی، پلان کاری که توسط دفتر داکار ارائه میگردد انجام گیرد.
- 12. قرارداد گیرنده مکلف است تا ساحه را از وجود خاک و سنگ اضافی بطور مکمل بعد از ختم کار پاک کاری نماید.

Contractor's Responsibilities:

<u>مسئولیت های قرارداد گیرنده:</u>

- 1. Start and completion dates for contract shall be according to work plan in Annex (II).
- 2. Contractor should commit no less than the agreed fixed number of required drilling rigs to each DACAAR project. Contractor must seek written approval to remove any drilling rig from DACAAR project to any other work place.
- 3. Contractor is responsible for the logistics costs during shifting / transportation of equipment between wells in project area.
- 4. Breakdowns or other delays during the work are not acceptable to DACAAR, in case any problem occurs; it must be report to DACAAR relevant field office immediately.
- 5. The Contractor should use river washed sand sorted gravel 2-6 (mm) for filling around filter. Contractor may use impermeable material for backfilling of around casing but still confirmation of the field officer is necessary on amount of back filling for screen and casings, it should be noted that, the cost of Gravel packing is separate, and cost of impermeable materials is separate.
- The Contractor will be fully responsible for vertical straight bore holes.
- 7. Where the water table is less than 5 meters, the upper part of well should be sealed with impervious clay to prevent the well from the contamination.
- 8. If the drilled well provides turbid unsafe water, that is the responsibility of contractor to rectify the problem; Otherwise, DACAAR will not pay for wells providing turbid water.
- 9. The contractor does not have the right to make contract with another party.
- 10. During the back filling, using of heavy machine is prohibited, only shovel should be used.

- 1. تاریخ شروع و ختم کار مطابق پلان کاری که در است ضمیمه (II) ذکر گردیده صورت گیرد.
- قرارداد گیرنده مکلف است تا حفاری چاه ها را در زمان معینه آن به اتمام رساند، در صورت استفاده از ماشین های بکار گذاشته شده برای داکار غرض اجرای برنامه های خارج از قرارداد باید اجازه نامه رسمی داکار را اخذ نماید.
- 3. مصارفات انتقال و نصب ماشین حفاری مسئولیت قرارداد گیرنده میباشد، داکار هیچگونه مسئولیت لوجستکی و یا اداری را در این زمینه ندارد.
- هیچگونه تأخیر ویا توقف کاری در جریان اجرأ قرارداد مجاز نیست و در صورت بروز مشکل فوراً داکار ساحوی مربوطه داکار در جریان گذاشته شود.
- 5. اطراف پایپ و فاتر توسط جغل دریایی سورت، لشم و شسته شده به سایز 2 الی 6 (ملی متر) و گل غیر قابل نفوذ مطابق به دیزاین چاه پرکاری گردد، مقدار پرکاری در اطراف فاتر و پایپ توسط انجنیر ساحه تثبیت میگردد، که این تصمیم با در نظرداشت ساحه صورت میگیرد، قابل تذکر است که قیمت پرکاری توسط ریگ شسته شده دریایی جدا است و قیمت خاک غیر قابل نفوذ جدا است و از جمله مسؤلیت های قرارداد گیرنده میباشد.
- مسیر عمق چاه ها باید عمود باشد و قرارداد گیرنده مسئولیت راست بودن عمق چاه ها را به عهده دارد.
- 7. در چاه هائیکه سطح آب کمتر از پنج متر باشد، قرارداد گیرنده مکلف است تا به منظور جلوگیری از عبور آب های ملوث قسمت های فوقانی پایپ را توسط گل غیر قابل نفوذ بسته نماید.
- 8. در صورتیکه آب چاه نا صاف، گل آلود ویا غیر قابل شرب باشد، قرارداد گیرنده مکلف است تا آنر تصحیح و بر طرف نماید. داکار پول آن چاه که دارای آب نا صاف باشند نمی پردازد.
- 9. قرارداد گیرنده حق ندارد که با شخصی دیگر این پروژه را قرارداد نماید.
- 10. پرکاری اطراف پایپ و فلتر توسط بیل صورت گیرد نه با کراچی و ماشین های ثقیل.

DACAAR Responsibilities:

مسئولیت های داکار:

- 1. Timely supply of materials from DACAAR's field offices: sufficient (boring length plus 3 meters) 4, inch diameter uPVC pipes for lining of the wells and one 4-meter filter per well.
- 2. DACAAR's representative will be present at site for monitoring of well drilling and physical test of water.
- 3. The Locations of the wells will be determined by DACAAR only. In case that contractor relocates a well without first obtaining DACAAR relevant regional office written approval then DACCAR will not be liable to make any payment for the well.
- 4. Payment will be made after successfully completion of each tube well against receipt of invoice and confirmation of DACAAR relevant field office authorized representative.
 - This is worth mentioning that DACAAR relevant field office must prepare the work progress on monthly basis and submit it to DACAAR relevant regional office.
- 5. In case of bad or salty water in the well the materials for blocking of the well (cement, and stone powder, or an equivalent) will be provided by DACAAR and the cost of labour for blocking will be paid by Contractor.
- DACAAR will pay Contractor according to fixed price in the contract.
- DACAAR is not responsible for security or any damages (human or machinery) caused during implementation of contract.

Terms of the Contact:

- 1. Start and completion of drilling work shall be based on the work plan in annex (II) of this contract.
- 2. In case of delays caused by the contractor, 0.5% of remaining work will be charged as delays penalty on each day of delay, this role is applicable till one month, after one to two month 20% penalty, delaying more than two months, will be caused penalty of 30%.

- رساندن به وقت مواد از دفاتر ساحوی داکار: مواد شامل پایپ 4 انچ یو پی وی سی برای سطر کردن چاه ها و یک فاتر چهار متره برای تصفیه آب هر چاه میباشد.
- نماینده داکار در بخش نظارت از جریان حفاری و تست فزیکی آب در ساحه حضور خواهد داشت.
- 3. موقیعت چاه فقط توسط نماینده رسمی داکار تعین میگردد، اگر قرارداد گیرنده به خواست خود موقیعت چاه را بدون همآهنگی قبلی دفتر منطقوی مربوطه داکار تغییر میدهد، در آنصورت داکار در قسمت پرداخت پول این نوع چاه هیچگونه مسؤلیت نخواهد داشت.
- 4. پرداخت پول در مقابل رسید انوایس بعد از تصدیق نماینده با صلاحیت داکار از ختم مؤفقانه هر چاه توسط دفتر ساحوی داکار در ولایت مربوطه قابل اجرأ میباشد.
- قابل یاد آوریست که گذارش از پیشرفت کار بطور ماهوار توسط انجنیر ساحوی ترتیب و تنظیم گردیده و به دفتر منطقوی مربوطه ارسال میگردد.
- 5. در صورت پایین بودن کیفیت آب و یا شور بودن طعم آن مواد مورد ضرورت از قبیل پودر سنگ و سمنت غرض بسته نمودن چاه مذکور توسط داکار تهیه خواهد گردید، و قیمت کارگری غرض بسته کردن چاه توسط قر ار داد گیر نده بر داخت خواهد شد.
- 6. پرداخت اجوره حفر چاه ها مطابق قیمت تعین شده در
 قر ار داد میباشد.
- داکار مسئولیت امنیتی و یا حوادث غیر مترقبه مانند خسارات مالی و یا جانی را در جریان اجرا قرارداد به عهده ندار د.

شرايط امضاً قرارداد:

- 1. شروع و ختم حفر چاه ها باید مطابق پلان کاری لست ضمیمه (II) قرار داد باشد.
- 2. در صورت تأخیر بدون موجب از طرف قرارداد گیرنده در حفر چاه ها مبلغ %0.5 بطور جریمه در بدل هر روز از کار باقی مانده از قرارداد گیرنده وضع میگردد، تأخیر از یکماه الی دو ماه %20 جریمه دارد و تأخیر بیشتر از دو ماه %30 جریمه را باعث میگردد.

- 3. Contractor should complete their contract in specified time. Delays due to natural disaster, war, and insecurity as well as some other logical reasons will be considered and the contractor must provide suitable narration and evidence in order to help the mutual consent.
- 4. The sites for the wells will be selected by DACAAR, and the contractor does not have right for selection of location for well.
- 5. Transportation cost of machineries, food and accommodation will be contractor's responsibility.
- 6. The contractor should complete the contract on time according to the given work plan. DACAAR reserve the right to terminate the contract without any compensation paid by DACAAR in case of any deviation in project completion or quality of work.
- 7. One- week prior notice will be given for contract termination. The payment will be made only for the work completed under specification. The contractor will return all unused materials given by DACAAR.
- 8. If the contractor works for three consecutive days in presence of DACAAR representative faced with any problem (hardness of the earth) and cannot go deeper, in that case DACAAR will pay for the drilled portion and will change the location for the drilling of another tube well.
- The contractor should confirm his active presence and activities during first weeks, after signing of the contract, otherwise, DACAAR will take a decision regarding cancellation of the contract.
- 10. Award of Contract will be based on the capacity/potentiality of bidder which will be decided after evaluation of the bidders. It is the right of DACAAR to make the decision of awarding contract.
- 11. DACAAR Technical Evaluation will be based on experience in drilling field, number of rig machines, status of machines, and knowledge about the targeted regions.

- 3. قرارداد گیرنده باید قرارداد را در وقت معینه آن اتمام رساند. مشکلات چون امنیت، آفات طبیعی وغیره دلایل منطقی است ثنا بوده، و قرارداد گیرنده باید توضیحات لازم را برای مؤسسه داکار فراهم نماید تا قناعت جانبین حاصل گردد.
- انتخاب ساحه برای حفر چاه توسط نماینده رسمی داکار صورت میگیرد، و قرارداد گیرنده حق انتخاب ساحه را ندارد.
- قیمت انتقال ماشین آلات، غذا، سرپناه مسئولیت قرار داد گیرنده میباشد.
- 6. قرارداد گیرنده باید قرارداد را در وقت معینه آن طبق پلان داده شده تکمیل نماید. در صورت عدم تطبیق برنامه ها مطابق پلان تعین شده و یا پائین بودن کیفیت کارها، داکار حق فسخ قرارداد را دارد و پول تضمین قابل باز پرداخت نمیباشد.
- 7. در صورت فسخ قرارداد، قرارداد گیرنده در ظرف یک هفته رسماً اطلاع خواهند یافت و تنها کارهایکه مطابق مشخصات تعین شده اجرا گردیده باشد قابل پرداخت میباشد. تمام مواد تهیه شده داکار که استفاده نگردیده باشد باید دوباره به داکار وایس گردد.
- در صورتیکه قرارداد گیرنده سه روز پی هم در حضور نماینده داکار بنابر موانع چون (سختی زمین) موفق به ادامه حفر چاه نگردد. در این صورت داکار فقط قیمت چاه حفر شده را خواهد پرداخت و موقعیت چاه بعدی توسط داکار تغیر داده میشود.
- 9. قرارداد گیرنده باید در هفته نخست حضور فعال و کاری خود را در ساحه به اثبات برساند، در غیر آن داکار در قسمت فسخ قرارداد و تصامیم لازمه اقدام خواهد نمود و نماینده داکار باید دفتر مرکزی را عندالموقع در جریان بگذارد.
- 10. قرارداد به اساس ظرفیت و توانایی قرارداد گیرنده بعد از ارزیابی داوطلب صورت میگیرد، البته داکار حق تصمیم گیری در این زمینه را دارا میباشد.
- 11. ارزیابی تخنیکی داکار به اساس تجربه در بخش حفاری، تعداد ماشین ها، وضعیت ماشین ها، داشتن معلومات کافی از ساحه تعین شده انجام خواهد شد.

- 12. Offers without thumb, signature or stamp and containing manipulation/overwriting in prices will be rejected automatically and the bidders have no right to complain.
- 13. DACAAR (Logistics Unit) adheres to National and International laws on child labour DACAAR makes sure all its suppliers and vendor abide by such laws preventing child labour in all DACAAR activities countrywide.
- 14. The Humanitarian Organizations (HO) may conduct on-site visit in the contractor's premises (or may take similar measures) to ensure compliance.
- 15. DACAAR reserves the right to make the decision to split the contract into different Contractors district wise as well.

- 12. آفر بدون شصت، امضاً، مهر و قلم خوردگی در قیمت بطور اتومتیک رد گردیده و داوطلب حق شکایت را ندارد.
- 13. دفتر داکار (شعبه لوژیستیک) با درنظرداشت قوانین ملی و بین المللی برای جلوگیری از کار کودکان مصمم بوده و سعی میکند که تمام فعالیتهای تهیه کننده گان و مشتریان این اداره به این اصل پابند باشند.
- 14. سازمان های بشر دوستانه (HO) ممکن است تا از محلات و سایت ها به بخاطر اطمینان خاطر و تطبیق درست کار توسط قرار داد گیرنده بازدید بعمل آورده ویا ممکن است اقدامات مشابه را انجام دهد.
- 15. داکار حق تصمیم گیری را برای تقسیم قرارداد به قسمت های مختلف به اساس ولسوالی ها را دارا میباشد.

For more details, please visit DACAAR Logistics Unit Main Office Kabul, Sunday through Thursday, from 8:00am to 03:00pm. Or contact on below Email Address: jamal@dacaar.org or wasimullah@dacaar.org

Sincerely Yours,

Manager – Logistics Unit

Date: June 27, 2024

ANNEX (I) Budget Breakdown / فورم آفر DACAAR RFQ 61 PRF-414 and 415/ECHO/2401-ECHO/EHWR1.3.7/06.2024

Lot I: Drilling of 14 Tube Wells by Heavy Percussion Rig for ECHO Project in Ghazni Province:

S/N	Drilling by Percussion Rig	Total No of Wells / تعداد چاه ها	UNIT COST PI			
	ولسوالی/ قریه Village/District		Drilling Well by Percussion rig and using of bucket not less than 10" diameter	Lowering of 4" PVC Pipe and Filter (Only pipe and Filter lowering wage)	Backfilling by impervious clay and Gravel packing by sorted and washed river gravel size (2-6 mm according the well design). The price should include costs of materials and backfilling wages.	Total Unit Cost/ Per Meter Including 2/7% Government Tax (AFN)
1	Ander District of Ghazni Province	7 Tube Well (60M depth)				
2	Dah Yak District of Ghazni Province	7 Tube Well (60M depth)				

Company / Individual Name:	اسم شرکت / آفر دهنده:
Address and Stamp:	آدرس و مهر کمپنی
Mobile No:	نمبر موبائيلنمبر موبائيل
Email Address:	ايمل آدرس

ANNEX (I) Budget Breakdown / فورم آفر DACAAR RFQ 59 PRF-411 and 412/ECHO/2401-ECHO/EHWR1.3.7/06.2024

Lot II: Drilling of 14 Tube Wells by Heavy Percussion Rig for ECHO Project in Maidan Wardak Province:

	Drilling by Percussion Rig		UNIT COST PI			
S/N	ولسوالي/ قريه Village/District	Total No of Wells / تعداد چاه ها	Drilling Well by Percussion rig and using of bucket not less than 10" diameter	Lowering of 4" PVC Pipe and Filter (Only pipe and Filter lowering wage)	Backfilling by impervious clay and Gravel packing by sorted and washed river gravel size (2-6 mm according the well design). The price should include costs of materials and backfilling wages.	Total Unit Cost/ Per Meter Including 2/7% Government Tax (AFN)
1	Sayed Abad District of Maidan Wardak Province	7 Tube Well (60M depth)				
2	Chak-e-Wardak District of Maidan Wardak Province	7 Tube Well (60M depth)				

Company / Individual Name:	اسم شرکت / آفر دهنده:
Address and Stamp:	آدرس و مهر کمپنی
Mobile No:	نمبر موبائيل
Email Address:	ايمل آدرس

ANNEX (II) Tentative Work Plan پلان تخمینی کاری DACAAR RFQ 59 PRF-411 and 412/ECHO/2401-ECHO/EHWR1.3.7/06.2024

Drilling of 28 Tube Wells by Heavy Percussion Rig for ECHO Project in Ghazni and Wardak Provinces:

Province	District	No of Wells	No of Percussion Rigs	Start of Work	Completion of Work	
	Ander	7	2		August 15, 2024	
Ghazni	Dah Yak	7	2	Starts Upon DACAAR		
Maidan	Sayed Abad	7	2	Contract Final Approval		
Wardak	Chak-e-Wardak	7	2			