

Organisation For Relief Development (ORD)  
Bill of Quantity  
Lot-3



Project Title: School Building Renovation(Building Repairing )  
Location: Baragh Girls High school, Kohistan District, Badakhshan Province.  
Subject: BoQ / Price Sheet of Lot-3  
Date: 01 September 2024

Annex-1

No.	Description	Amount <sup>*)</sup> [AFN]
-----	-------------	-------------------------------

Summary:

1	A- School Building Revolution (Repairing) of Baragh Girls High school in Kohistan District, Badakhshan Province.	
2		
3		
4		
5		
Grand Total		

\*) including all tax according to income tax manual of Ministry of Finance; government of Afghanistan

Total Price in words:

Company Name:	
Date:	
Signature:	
Stamp	

No.	Description	Unit	Quantity	Unit cost <sup>1)</sup> [AFN]	Amount <sup>1)</sup> [AFN]
A	<b>A- School Building Revolution (Repairing) of Baragh Girls High school in Kohistan District, Badakhshan Province.</b>				
A	<b>A. Civil Works:</b>				
A1	<b>Repairing leakage of a total 667 Square meters Roof with 24 gage Gi sheets piece, Silicon, and washer screw and wooden plank 6x4cm and 10m2 new Iron sheet is required in roof corner and hump.</b> Prepare all materials, equipment, and manpower for Repairing the leakage of a total 667 Square meters Roof with 24 gage Gi sheets piece, Silicon, and washer screw with all related activities to complete the job as per drawing and instruction of the in-charge engineer All tasks for this item to be under full approval in charge engineer	M <sup>2</sup>	667		
A2	<b>Supply and installation of false ceiling 60x60cm plastic with its chenels and shutter "chifti"</b> Prepare all materials, equipment, and manpower for supplying and installation of false ceiling completed with all required activities and instruction of the in-charge engineer All tasks for this item are to be under full approval in charge engineer	M <sup>2</sup>	420		
A3	<b>Interior wall cement plaster 1:4 including cement grout 1:1.</b> Prepare all materials, equipment, and manpower for interior wall cement Plaster 1:4 and cement sand grout 1:1 before plaster work on existing stone wall including stoen wall surfacing and cleaning and during complete the job as per drawing and instruction of the in-charge engineer All tasks for this item are to be under full approval in charge engineer	M <sup>2</sup>	1053		
A4	<b>Removing existing damaged veranda and sidewalk's PCC</b> Prepare all materials, equipment, and manpower for Removing existing damaged verabda PCC and sidewalk PCC with all related activities to complete the job as per drawing and instruction of the in-charge engineer all waste materials and debris are to be transported to the approved damp site. All tasks for this item are to be under the full approval of the charge engineer	M <sup>3</sup>	19.3		
A5	<b>Stone Pitching Work: under class floor, sidewalks with 10cm thickness</b> Prepare all materials, equipment, and manpower for stone pitching with all related activities to complete the job as per drawing and instruction of the in-charge engineer all waste materials and debris are to be transported to the approved damp site. All tasks for this item are to be under the full approval of the charge engineer	M <sup>3</sup>	15.6		
A6	<b>PCC work Mark 150 1:2:4 with 6cm thickness for veranda, sidewalks and ramp</b> Prepare all materials, equipment, and manpower for PCC work including best quality of sand, fresh cement, clean water and crash gravel with all related activities to complete the job as per drawing and instruction of the in-charge engineer all waste materials and debris are to be transported to the approved damp site. All tasks for this item are to be under the full approval of the charge engineer	M <sup>3</sup>	9.4		
A7	<b>Adjusting and repairing wooden doors and replacement its peice "Pala" , right and bottom frame and hardware's, locks and broken glass</b> Prepare all materials, equipment, and manpower for Adjusting and repairing wooden doors and replacement of door peice 9(1.9x0.85), hardware and broken glass with all related activities to complete the job as per drawing and instruction of the in-charge engineer All tasks for this item are to be under full approval in charge engineer	M <sup>2</sup>	47.5		
A8	<b>Adjusting and repairing wooden windows with replacement of window's hardware and broken glass including fly screen within cheftis</b> Prepare all materials, equipment, and manpower for Adjusting and repairing wooden windows and replacement of windows hardware and broken glass + including fly screen within cheftis and with all related activities to complete the job as per drawing and instruction of the in-charge engineer All tasks for this item are to be under full approval in charge engineer	M <sup>2</sup>	89.5		
A9	<b>Plastic Paint interior walls 100% three coats</b> Prepare all materials, equipment, and manpower for the wall 100% Plastic Paint three coats (Jotun or equivalent) including preparation, primer, and filling with all related activities to complete the job as per drawing and instruction of the in-charge engineer All tasks for this item are to be under full approval in charge engineer	M <sup>2</sup>	1033		
A10	<b>Painting of stone masonry with varnish paint three coats</b> Prepare all materials, equipment, and manpower for the Painting of stone masonry with varnish paint three coats including stone masonry surface preparation, and primer with all related activities to complete the job as per drawing and instruction of the in-charge engineer All tasks for this item are to be under full approval in charge engineer	M <sup>2</sup>	392		

No.	Description	Unit	Quantity	Unit cost <sup>7)</sup> [AFN]	Amount <sup>7)</sup> [AFN]
A11	<b>Oil Painting of doors and windows three coats+black board</b> Prepare all materials, equipment, and manpower for window and door oil painting with all related activities to complete the job as per drawing and instruction of the in-charge engineer all waste materials and debris are to be transported to the approved damp site. All tasks for this item are to be under the full approval of the charge engineer	M <sup>2</sup>	160		
A12	<b>Supply and installation of chimney caps Gi Sheet 0.5mm</b> Prepare all materials, equipment, and manpower for chimney caps with all related activities to complete the job as per drawing and instruction of the in-charge engineer all waste materials and debris are to be transported to the approved damp site. All tasks for this item are to be under the full approval of the charge engineer	Pic	12		
A13	<b>Supply and installation of handrail for ramp with three coats.</b> Prepare all materials, equipment, and manpower for the preparation of 17m length 80cm high with 3inch dia best quality and Painting of Steel handrails with oil paint on three coats with all related activities to complete the job as per drawing and instruction of the in-charge engineer All tasks for this item to be under full approval in charge engineer	ml	17		
A14	<b>Site prepration and cleaning from extra soil and construction materials</b> Prepare all materials, equipment, and manpower for Cleaning the project site from extra soil, grass, and materials with all related activities to complete the job as per the in-charge engineer all waste materials and debris are to be transported to the approved damp site. All tasks for this item are to be under the full approval of the charge engineer	Job	1		
A15	<b>Donor Metal Sign Board 120x80cm as per design and drawings</b>	Pic	1		
<b>A</b>	<b>Sub total cost for (A. Civil Works)</b>				
	<b>Grant Total Price (A)</b>				