

Organisation For Relief Development (ORD)
Bill of Quantity
Lot-5



Project Title: School Building Renovation (Building Repairing)
Location: Ainuddin Shaheed Hgh School in Shahr I Buzurg District, Badakhshan Province.
Subject: BoQ / Price Sheet of Lot-5
Date: 01 September 2024

Annex-1

No.	Description	Amount ^{*)} [AFN]
-----	-------------	-------------------------------

Summary:

1	A- School Building Renovation (Building Repairing) in Aainuddin Shaheed Hgh School , Shahr I Buzurg District, Badakhshan Province.	
2		
3		
4		
5		
Grand Total		

*) including all tax according to income tax manual of Ministry of Finance; government of Afghanistan

Total Price in words:

Company Name:	
Date:	
Signature:	
Stamp	

No.	Description	Unit	Quantity	Unit cost ¹⁾ [AFN]	Amount ¹⁾ [AFN]
A	A- School Building Renovation (Building Repairing) in Aainuddin Shaheed Hgh School , Shahr I Buzurg District, Badakhshan Province.				
A	A. Civil Works:				
A - 1	<u>Roofing Repairing work including "Installation of Iron sheet and wooden sheet to destroyed parts.</u> Prepare all materials, equipment, and manpower for providing roof wooden Sheet Destroyed parts, Repair and cleaning of gutters and Modify parts of iron sheet on the wooden trass with all related activities to complete the job as per drawing and instruction of the in-charge engineer All tasks for this item to be under full approval in charge engineer	M ²	67.432		
A - 2	<u>Removing existing damaged Stair's PCC</u> Prepare all materials, equipment, and manpower for Removing existing damaged Stair PCC with all related activities to complete the job as per drawing and instruction of the in-charge engineer all waste materials and debris are to be transported to the approved damp site. All tasks for this item are to be under the full approval of the charge engineer	M ³	0.945		
A - 3	<u>PCC work Mark 150 1:2:4 for srairs</u> Prepare all materials, equipment, and manpower for PCC work including best quality of sand, fresh cement, clean water and crash gravel with all related activities to complete the job as per drawing and instruction of the in-charge engineer all waste materials and debris are to be transported to the approved damp site. All tasks for this item are to be under the full approval of the charge engineer .	M ³	1.323		
A - 4	<u>Interior and exterior wall plaster 1:4 and Removing existing damaged</u> Prepare all materials, equipment, and manpower for exterior and interior wall cement and sand Plaster 1:4 with all related activities to complete the job as per drawing and instruction of the in-charge engineer All tasks for this item are to be under full approval in charge engineer	M ²	43		
A - 5	<u>Repair of Interior and exterior wall hairline cracks:</u> Prepare all materials, equipment, and manpower for Removing the Repair of hairline cracks with all related activities to complete the job as per drawing and instruction of the in-charge engineer all waste materials and debris are to be transported to the approved damp site. All tasks for this item are to be under the full approval of the charge engineer	M	55		
A - 6	<u>Installation of Damaged glazing for 14 windows (120 x 40,90x70) with wooden chefti 1.5cm = 100m, glasses 3mm</u> Prepare all materials, equipment, and manpower for Installation of Damaged glazing for 14 windows (120 x 40,90x70) with wooden chefti 1.5cm = 100m, glasses 3mm with all related activities to complete the job as per drawing and instruction of the in-charge engineer all waste materials and debris are to be transported to the approved damp site. All tasks for this item are to be under the full approval of the charge engineer	M ²	23.94		
A - 7	<u>Installation of fly screen for 40 windows</u> Prepare all materials, equipment, and manpower for Installation of fly screen for 40 windows with all related activities to complete the job as per drawing and instruction of the in-charge engineer all waste materials and debris are to be transported to the approved damp site. All tasks for this item are to be under the full approval of the charge engineer	M ²	25.2		
A - 8	<u>Adjusting wooden doors and replacing door Lock</u> Prepare all materials, equipment, and manpower for 8 doors lock and. Frame adjustment for 8 doors with all related activities to complete the job as per drawing and instruction of the in-charge engineer All tasks for this item are to be under full approval of the in-charge engineer	pic	8		
A - 9	<u>Wall interior and exterior 100% Plastic Paint three coats</u> Prepare all materials, equipment, and manpower for the wall 100% Plastic Paint three coats (Jotun or equivalent) including preparation, primer, and filling with all related activities to complete the job as per drawing and instruction of the in-charge engineer All tasks for this item are to be under full approval in charge engineer	M ²	2460.742		
A - 10	<u>Oil Painting doors and windows three coats+black board</u> Prepare all materials, equipment, and manpower for the window and doors Paint three coats (Birage or equivalent) including preparation, primer, and filling with all related activities to complete the job as per drawing and instruction of the in-charge engineer All tasks for this item are to be under full approval in charge engineer	M ²	197.65		
A - 11	<u>Painting of stone masonry with varnish paint three coats</u> Prepare all materials, equipment, and manpower for the Painting of stone masonry with varnish paint three coats including stone masonry surface preparation, and primer with all related activities to complete the job as per drawing and instruction of the in-charge engineer All tasks for this item are to be under full approval in charge engineer	m2	101.22		

No.	Description	Unit	Quantity	Unit cost ⁷⁾ [AFN]	Amount ⁷⁾ [AFN]
A - 12	<u>Cleaning of the project site from extra soil, grass, and materials</u> Prepare all materials, equipment, and manpower for Cleaning the project site from extra soil, grass, and materials with all related activities to complete the job as per the in-charge engineer all waste materials and debris are to be transported to the approved damp site. All tasks for this item are to be under the full approval of the charge	LS	1		
A - 13	<u>Donor Metal Sign Board 120x80cm as per design and drawings</u>	Pic	1		
B - Renovation of existing 5 cabinets latrine					
A - 14	<u>Removing existing damaged floor, stairs and ramp's PCC</u> Prepare all materials, equipment, and manpower for Removing existing damaged floor PCC with all related activities to complete the job as per drawing and instruction of the in-charge engineer all waste materials and debris are to be transported to the approved damp site. All tasks for this item are to be under the full approval of the charge engineer	M ³	5.5		
A - 15	<u>Stone Pitching Work: under Latrin carridor, stairs, ramp and sidewalks</u> Prepare all materials, equipment, and manpower for stone pitching with all related activities to complete the job as per drawing and instruction of the in-charge engineer all waste materials and debris are to be transported to the approved damp site. All tasks for this item are to be under the full approval of the charge engineer.	M ³	6		
A - 16	<u>PCC work Mark 150 1:2:4 for classes floor and sidewalks</u> Prepare all materials, equipment, and manpower for PCC work including best quality of sand, fresh cement, clean water and crash gravel with all related activities to complete the job as per drawing and instruction of the in-charge engineer all waste materials and debris are to be transported to the approved damp site. All tasks for this item are to be under the full approval of the charge engineer	M ³	3		
A - 17	<u>Interior and exterior wall plaster 1:4 "cement and sand"</u> Prepare all materials, equipment, and manpower for exterior wall cement and sand Plaster 1:4 with all related activities to complete the job as per drawing and instruction of the in-charge engineer All tasks for this item are to be under full approval in charge engineer	M ²	18		
A - 18	<u>Instalation of new wooden doors</u> Prepare all materials, equipment, and manpower for 2 new doors with all related activities to complete the job as per drawing and instruction of the in-charge engineer All tasks for this item are to be under full approval in charge enginee	pic	2		
A - 19	<u>Adjusting wooden doors and replacement of door Lock</u> Prepare all materials, equipment, and manpower for 2 new doors with all related activities to complete the job as per drawing and instruction of the in-charge engineer All tasks for this item are to be under full approval in charge enginee	pic	4		
A - 20	<u>Plastic Paint three coats with Primer exterior wall and interior 100%</u> Prepare all materials, equipment, and manpower for the preparation of wall surfaces with Primer and filling and Paint the interior and exterior wall with 100% plastic paint with all related activities to complete the job as per drawing and instruction of the in-charge engineer All tasks for this item are to be under full approval in charge engineer	M ²	312		
A - 21	<u>Supply and installation of handrail for ramp with 23.5m length and 80cm high from GI pipe 3inch and Painting of Steel handrail with oil paint three coats.</u> Prepare all materials, equipment, and manpower for the preparation of Steel handrail surfaces and Painting of Steel handrails with oil paint on three coats with all related activities to complete the job as per drawing and instruction of the in-charge engineer All tasks for this item to be under full approval in charge engineer	L/M	23.5		
A - 22	<u>Oil Painting doors and windows three coats</u> Prepare all materials, equipment, and manpower for the metal windows and doors paint three coats (Birage or equivalent) including preparation, primer, and filling with all related activities to complete the job as per drawing and instruction of the in-charge engineer All tasks for this item are to be under full approval in charge engineer	M ²	14.25		
A - 23	<u>Roofing work including "Installation of Iron sheet to Destroyed parts .</u> Prepare all materials, equipment, and manpower for providing roof wooden Sheet Destroyed parts, Repair and cleaning of gutters and Modify parts of iron sheet on the wooden trass with all related activities to complete the job as per drawing and instruction of the in-charge engineer All tasks for this item to be under full approval in charge engineer	M2	32.67		
A	Sub total cost for (A. Civil Works)				
	Grant Total Price (A)				