



1-The casing material will be PVC or Steel pipe

2-The delivery pipe material will be PVC or galvanized Steel

3-Equivalent imperial distances the well must be :

- 50 M from sewage effluent discharge the ground surface.

- 100 M -from a sewage lagoon.

- 3-4 M from existing buildings.

- 6 M from the road and public highway.

NOTE-2:

for implementation & accomplishment of project , we need to the following investigation to be done :

1-site and environmental investigations.

2-geotechnical investigation.

3-hydrological investigation.

4-sampling.

ROTARY WELL.