

AS- BUILT & NEW
STRUCTURES


HERAT, FARSI, AFGHANISTAN

Identified Gaps for Existing WASH Services in Chaprod SHC:

- Lack of any water source for this clinic
- Lack of wash floor drain in (vaccination room, clinic hall and corridor)
- Absence of hand washing facilities (sink) in (clinic hall) and clinic area.
- Need to new water Tanks (the existing water tank volume is not enough with low quality need to change) and insulation storage tanks
- Need to provide garbage containers inside the Clinic building
- Need to create a ramp and stair for the entrance gate of existing male and female toilets
- Absence of electricity system for the clinic (all rooms of clinic is without electricity)
- Some part of the building (vaccination room, new mix bath & toilet for delivery room and Hall) have no water supply system and sewerage system
- Existed Waste management is without any boundary protection, need some repairing
- The delivery room has no bath and toilet adjacent to it.
- The exiting mix bath and toilet need installation complete set of head shower.

Solution:

- -Construction a bore well in the clinic site by depth of 45m to prepare safe & clean water for the clinic
- Installation of the sinks in (clinic corridor and Hall) for hand washing facility
- Construction of one mix flash toilets & bath with all needed material for delivery room
- installation ramp and railing in existing male and female toilets
- Upgrading the existing mix toilet & bath for clinic staff (installation tiles, and head shower complete set)
- Installation sewerage pipe and Floor Drain in (vaccination room, hall, toilet and bath) connecting this system to existing septic tank
- installation one 200liters sun water boiler, one 500liters water tank with stand for sun water boiler, one 1000lite water tank for existing male and female toilets and one 2000liter water tank for clinic water supply system
- installation lights in clinic rooms, bath and toilets
- construction one public tap station in clinic area for location and details (drawing)
- installation of ceramic, cornice and tiles according to drawing
- installation fence around existing waste management system, installation waste management area (8x5M) with 5cm PCC for protection

TASK & RESPONSIBILITIES		DATE	NO OF PAGES 	PROVINCE	Herat	SCALE	-	PROJECT SUB TITLE	Major maintenace of HCF-WASH sector
SURVEYED BY	Zalal, Farjad	30-July-2024		DISTRICT	Farsi	START DATE	-	DRAWING TYPE	cover page
DRAWN BY	M.Ismael	15-8-2024		HCF NAME	Chaproad SHC	END DATE	-	E	63° 26' 5.893"
REVIEWED BY	Farid Ahmad Qaderi	-		HCF TYPE	SHC	PROJECT TITLE	FCDO-DAWAM	N	33° 56' 11.691"
APPROVED BY	Simon Wankuru	-							




TABLE OF CONTENT	
1	New Solar power system for water pump
2	Main clinic building
3	New 2000liter-horizontal water tank(high-density polyethylene 5layer tank)
4	New sun water Boiler 200lit
5	New 500 liter-horizontal water tank (high-density polyethylene 5 layer Tank) with stand for sun boiler
6	New toilet &bath for delivery room (2x1.5m)
7	Existed septic tank need to evacuation & cleaning and connect to new drain well
8	New drain dug well for septic tank
9	Existing male toilets
10	Existing female toilets
11	New 1000 liter-horizontal water tank (high-density polyethylene 5 layer Tank)
12	Existed Waste management need boundary fiance
13	Existing absorption well
14	Room for CHW
15	Guard room
16	New hand washing station
17	New bore-well with depth of 45m

TASK & RESPOSIBILITIES		DATE	NO OF PAGES	PROVINCE	Herat	SCALE	1:200	PROJECT SUB TITLE	Major maintenace of HCF-WASH sector
SURVEYED BY	Zalal, Farjad	30-July-2024		DISTRICT	Farsi	START DATE	----	DRAWING TYPE	Site plan
DRAWN BY	M.ismael	15-8-2024	2 8	HCF NAME	Chaproad SHC	END DATE	----	E	63° 26' 5.893"
REVIEWED BY	Farid Ahmad Qaderi	-		HCF TYPE	SHC	PROJECT TITLE	FCDO-DAWAM	N	33° 56' 11.691"
APPROVED BY	Simon Wankuru	-							

act!onaid





TABLE OF CONTENT FOR BUILDING PLAN

S	New hand washing sink complete sit with mirror
S, T, T'	Existing hand washing Sink, dish-washing sink eastern WC and western WC(all sinks and WC with pink color already exist in the clinic)
T	Stand WC washbasin
T'	Sitting WC washbasin
H	New head shower complete sit

-Due to lack of floor drain inside the clinic hall, corridor, and vaccination room we planed to install floor drain and also install sinks in(clinic hall and corridor)

- The sinks must be installed which is numbered in the plan by S in total there are 14 sink in the drawing which 11 of them are permanently installed and we need to install 3 remained hand washing sinks in the clinic which is highlighted with white color also two stand WC and two set head shower need to install



-Need to create a ramp and railing for the entrance gate of men and women's toilets for disabled people



act:onaïd

TASK & RESPOSIBILITIES		DATE	NO OF PAGES	PROVINCE	Herat	SCALE	1:100	PROJECT SUB TITLE	Major maintenace of HCF-WASH sector
SURVEYED BY	Zalal, Farjad	30-July-2024		DISTRICT	Farsi	START DATE	----	DRAWING TYPE	Main plan
DRAWN BY	M.ismael	15-8-2024	3 8	HCF NAME	Chaproad SHC	END DATE	----	E	63° 26' 5.893"
REVIEWED BY	Farid Ahmad Qaderi	-		HCF TYPE	SHC	PROJECT TITLE	FCDO-DAWAM	N	33° 56' 11.691"
APPROVED BY	Simon Wankuru	-							


TABLE OF CONTENT FOR Tile and ceramic PLAN

	New ceramic planed area
	New Tile planed area


-The ceramic and tile hatched areas are under plan to be install ceramic and tile
 -Due to the installation of hand washing sinks(clinic corridor and hall), floor drains(hall, vaccination room mix bath & toilet) and connection the water supply pipe (mix bath & toile in deliver room, tap-station, all sinks in hall), it is necessary to demolish the existing ceramic floor. The contractor should provide ceramic tiles that match the exact size and color of the existing ceramic tiles (color white, 40x40 cm). The maximum demolition width should be one meter, and all cuts should be made in a direct line to maintain the floor's aesthetic appeal.



Clinic floor tile picture



act:onaïd

TASK & RESPOSIBILITIES		DATE	NO OF PAGES 	PROVINCE	Herat	SCALE	1:100	PROJECT SUB TITLE	Major maintenace of HCF-WASH sector
SURVEYED BY	Zalal, Farjad	30-July-2024		DISTRICT	Farsi	START DATE	----	DRAWING TYPE	Tile& Ceramic plan
DRAWN BY	M.ismael	15-8-2024		HCF NAME	Chaproad SHC	END DATE	----	E	63° 26' 5.893"
REVIEWED BY	Farid Ahmad Qaderi	-		HCF TYPE	SHC	PROJECT TITLE	FCDO-DAWAM	N	33° 56' 11.691"
APPROVED BY	Simon Wankuru	-							

PPR pipe 32mm


Hand Washing Top View

Note:

- Red color line indicates hot water pipe line
- Blue color line indicates cold water pipe line
- The hot and cold PPR water pipe already installed in all existing sinks, we will conned the new sinks, shower and WCs.
- we will connect new water supply pipe from (connection water to hand-washing sink in hall from water pipe of existing bath, connection water to new mix bath & toilet for delivery room and tap-station from delivery room's sink)
- The pipes diameter for the supplying system are: PPR pipe 25mm for distribution hot and cold water, 32mm PPR pipe is for transferring water from sources to the distribution pipes and tap-station for more detail search in BoQ

PPR pipe 25mm

act:onaid

TASK & RESPOSIBILITIES		DATE	NO OF PAGES 	PROVINCE	Herat	SCALE	1:100	PROJECT SUB TITLE	Major maintenace of HCF-WASH sector
SURVEYED BY	Zalal, Farjad	30-July-2024		DISTRICT	Farsi	START DATE	----	DRAWING TYPE	Water supply plan
DRAWN BY	M.ismael	15-8-2024		HCF NAME	Chaproad SHC	END DATE	----	E	63° 26' 5.893"
REVIEWED BY	Farid Ahmad Qaderi	-		HCF TYPE	SHC	PROJECT TITLE	FCDO-DAWAM	N	33° 56' 11.691"
APPROVED BY	Simon Wankuru	-							

CHAPROD SHC WASTE WATER DRAINAGE PLANNED SYSTEM

Note:




This form indicates swab




This form indicates siphon

Note:


- The existing sewerage system of clinic is functionally work we will connect new sinks, floor drains, W.C.s and tap- station's drainage pipe to the existing septic tank.
- For the kitchen there is a absorption dug well with depth of 5m we will connect the new drainage pipe to it




act:onaïd

TASK & RESPOSIBILITIES		DATE	NO OF PAGES 	PROVINCE	Herat	SCALE	1:100	PROJECT SUB TITLE	Major maintenace of HCF-WASH sector
SURVEYED BY	Zalal, Farjad	30-July-2024		DISTRICT	Farsi	START DATE	----	DRAWING TYPE	WASTE WATER DRAINAGE
DRAWN BY	M.ismael	15-8-2024		HCF NAME	Chaproad SHC	END DATE	----	E	63° 26' 5.893"
REVIEWED BY	Farid Ahmad Qaderi	-		HCF TYPE	SHC	PROJECT TITLE	FCDO-DAWAM	N	33° 56' 11.691"
APPROVED BY	Simon Wankuru	-							


Hand Washing Top View




Front View



Section C-C



Section B-B



	TASK & RESPOSIBILITIES		DATE		PROVINCE	Herat	SCALE	1:100	PROJECT SUB TITLE	Major maintenace of HCF-WASH sector
	SURVEYED BY	Zalal, Farjad	30-July-2024		DISTRICT	Farsi	START DATE	----	DRAWING TYPE	Tap-Station
	DRAWN BY	M.ismael	15-8-2024		HCF NAME	Chaproad SHC	END DATE	----	E	63° 26' 5.893"
	REVIEWED BY	Farid Ahmad Qaderi	-		HCF TYPE	SHC	PROJECT TITLE	FCDO-DAWAM	N	33° 56' 11.691"
	APPROVED BY	Simon Wankuru	-							

