

BOQ for Rehabilitation of Masamot SHC

HF N	S/No	ACTIVITIES	Unit	Quantity	Unit Cost Af	Total Cost Af	Remarks
Masamot SHC 3	1	compaction and leveling of old Clay and spread one layer of low Quality plastic	M ²	120.00			
	2	straw clay (mud plaster) of roof Thickness 3.5cm , straw =1kg/meter	M ²	120.00			
	3	Supply and installation water tap, piping all related valve ,Tee , elbow, and joint based on the need and with all required activities.	set	2.00			
		GRAND TOTAL					

BOQ for Rehabilitation of Gamba DH

HF N	S/No	ACTIVITIES	Unit	Quantity	Unit Cost Af	Total Cost Af	Remarks
Gambah DH 5	1	Compaction and leveling of old Clay and spread one layer of low Quality plastic	M ²	200			
	2	PCC ccement concrete for Roof ,Gravel , local Laghman yelo send and M ; !00 1:3:6 ,Thickness = 5cm	M ²	200			
	3	Roofing ; Supply and Installationone layer Bituminous (Isogam) waterproofed, one Roll 40kg L= 10meter and W=1meter with all related works for roof.	M ²	210			
	4	Replacement of tap , mixer, and extra pipe for sink and water tank of commode with all required activities:	set	12			
		GRAND TOTAL					

BOQ for Rehabilitation of Paitak BHC

HF N	S/No	ACTIVITIES	Unit	Quantity	Unit Cost Af	Total Cost Af	Remarks
Paitak BHC 6	1	Compaction and leveling of old Clay and spread one layer of low Quality plastic	M ²	120.00			
	2	PCC ccement concrete for Roof ,Gravel , local Laghman yelo send and M ; !00 1:3:6 ,Thickness = 5cm	M ²	120.00			
	3	Roofing ; Supply and Installationone layer Bituminous (Isogam) waterproofed, one Roll 40kg L= 10meter and W=1meter with all related works for roof.	M ²	130.00			
		GRAND TOTAL					

MeI HF

BOQ for Rehabilitation of Mail SHC

HF N	S/No	ACTIVITIES	Unit	Quantity	Unit Cost Af	Total Cost Af	Remarks
Mail SHC 7	1	Leveling of roof and spread 2 layer of plastic best Quality	M ²	150.00			
	2	straw clay (mud plaster) of roof Thickness 3.5cm , straw =1kg/meter	M ²	150.00			
		GRAND TOTAL					

BOQ for Rehabilitation of Qalai Nagel BHC

HF N	S/No	ACTIVITIES	Unit	Quantity	Unit Cost Af	Total Cost Af	Remarks
Qalai Nagel BHC 9	1	Compaction and leveling of old Clay and spread one layer of low Quality plastic	M ²	300.00			
	2	PCC ccement concrete for Roof ,Gravel , local Laghman yelo send and M ; !00 1:3:6 ,Thickness = 5cm	M ²	300.00			
	3	Roofing ; Supply and Installationone layer Bituminous (Isogam) waterproofed, one Roll 40kg L= 10meter and W=1meter with all related works for roof.	M ²	320.00			
	4	For Wooden window & Door replcement and repiaring of all respected as lock , hinge , glass hand hangar and installation, accessories and Aluminum Fly Screens	piece	25.00			
		GRAND TOTAL					

BOQ for Rehabilitation of Shamakat BHC

HF N	S/No	ACTIVITIES	Unit	Quantity	Unit Cost Af	Total Cost Af	Remarks
Shamakat BHC 13	1	compaction and leveling of old Clay and spread one layer of low Quality plastic	M ²	300.00			
	2	PCC ccement concrete for Roof ,Gravel , local Laghman yelo send and M ; !00 1:3:6 ,Thickness = 5cm	M ²	300.00			
	3	Roofing ; Supply and Installationone layer Bituminous (Isogam) waterproofed, one Roll 40kg L= 10meter and W=1meter with all related works for roof.	M ²	310.00			
	4	for Wooden window & Door replicement and repiaring of all respected as lock , hinge , glass hand hangar and installation, accessories and Aluminum Fly Screens	piece LMS	10.00			
	5	for PVC window replicement and repiaring of all respected as lock , hinge , glass hand hangar and installation, accessories and Aluminum Fly Screens	piece LMS	20.00			
		GRAND TOTAL					

BOQ for Rehabilitation of Kail SHC

HF N	S/No	ACTIVITIES	Unit	Quantity	Unit Cost Af	Total Cost Af	Remarks
Kail SHC 14	1	Leveling of roof and spread 2 layer of plastic best Quality	M ²	190.00			
	2	Straw clay (mute plaster) of roof Thickness 3.5cm , straw =1kg/meter	M ²	165.00			
		GRAND TOTAL					

BOQ for Rehabilitation of Dogran BHC

HF N	S/No	ACTIVITIES	Unit	Quantity	Unit Cost Af	Total Cost Af	Remarks
Dogran BHC 21	1	Compaction and leveling of old Clay and spread one layer of high Quality plastic	M ²	190.00			
	2	Straw clay (mud plaster) of roof Thickness 3.5cm , straw =1kg/meter	M ²	190.00			
	3	Making and enstallation wooden partition wall with opening part for window frame size 6x6cm and board 1" Wood of kunar with all respected works	M ²	18.00			
	4	New Wooden Door and window wood main frame 12x7 cm and opaning part vertical , horizontally wood frame 9x4.5 cm with all respected as lock , hinge , glass hand hangar and installation, accessories and Aluminum Fly Screens	M ²	12.00			
		GRAND TOTAL					

BOQ for Rehabilitation of Karik SHC

HF N	S/No	ACTIVITIES	Unit	Quantity	Unit Cost Af	Total Cost Af	Remarks
Karik SHC 24	1	Compaction and leveling of old Clay and spread one layer of high Quality plastic	M ²	150.00			
	2	straw clay (mud plaster) of roof Thickness 3.5cm , straw =1kg/meter	M ²	150.00			
		GRAND TOTAL					

BOQ for Rehabilitation of Manjaghan SHC

HF N	S/No	ACTIVITIES	Unit	Quantity	Unit Cost Af	Total Cost Af	Remarks
Manjaghan SHC 25	1	Levelling of roof and spread 2 layer of plastic best Quality	M ²	130.00			
	2	straw clay (mute plaster) of roof Thickness 3.5cm , straw =1kg/meter	M ²	130.00			
	3	Wooden Door and window frame and opaning part , Repiaring with all respected as lock , hinge , glass hand hangar and installation, accessories and Aluminum Fly Screens	Piece	12.00			
	4	Delivery room repiaring (plaster , painting ,tiling and water sapply system)	LMS	1.00			
		GRAND TOTAL					

BOQ for Rehabilitation of Katwal Khando SHC

HF N	S/No	ACTIVITIES	Unit	Quantity	Unit Cost Af	Total Cost Af	Remarks
Katwal Khando SHC 42	1	Leveling of roof and spread 2 layer of plastic best Quality	M ²	120.00			
	2	Straw clay (mute plaster) of roof Thickness 3.5cm , straw =1kg/meter	M ²	120.00			
	3	Supply and installation of,3 socket , 3 holtar , 3 light 40w , swetch , one fuse with all wiring and with all required activities.	jop	1.00			
		GRAND TOTAL					

BOQ for Rehabilitation of Dawlatshah CHC

HF N	S/No	ACTIVITIES	Unit	Quantity	Unit Cost Af	Total Cost Af	Remarks
Dawlatshah CHC 43	1	Removing of old Metal sheet and wooden board and other materials of Valley (Gutter) on the roof and reinstallation of old Metal sheet wooden board with all required activities:	M ²	70			
	2	Removing of old Metal sheet on the roof and Parapet wall and reinstallation of old Metal sheet from area with all required activities:	M ²	90			
	3	PCC ccement concrete for Gatter of Roof , Gravel, local Laghman yellow sand and M 1:1.5:3 ,Thickness = 6 cm for floor of Gatter on the roof on the top of floor .	M ²	52			
	4	PCC ccement concrete for Gatter of Roof Gravel , local Laghman yelo send and M 1:1.5: 3 Thickness = 6 cm for side wall hight = 30 cm with sheetring and all related works	M ²	30			
	5	Mortar filing of M= 250 1.5:3 thickness 1.5cm cement and zero and 5mm chaps pet Luo powder and chaps powder with all associated works for floor of gatter .	M ³	70			
	6	Mortar filing of M= 250 1.5:3 thickness 0.7cm cement and zero chaps pet Luo powder and chaps powder with all associated works for wall of gatter	M ²	60			
	7	Tin (قلعي) mix of (zinc,Lead,Ammonium chloride and asid) filing of pore and hole for All roof and Valley gutter .	jop	1			
	8	Compaction and leveling of old Clay and spread one layer of low Qualty plastic	M ²	120			
	9	PCC ccement concrete for Roof ,Gravel , local Laghman yelo send and M ; !00 1:3:6 ,Thickness = 5cm	M ²	120			
	10	Roofing ; Supply and Installationone layer Bituminous (Isogam) waterproofed, one Roll 40kg L= 10meter and W=1meter with all related works for roof.	M ²	250			
		GRAND TOTAL					