

BOQ for Rehabilitation of Parwaye SHC

HF N	S/No	ACTIVITIES	Unit	Quantity	Unit Cost Af	Total Cost Af	Remarks
Parwaye PHC 37	1	Delivery Room Installation and suply of Floor tile 50x50 ceramic whith all respected works	M ²	22.00			
	2	Delivery Installation and suply of Wall tile 30x60 And rmoveing of wall Paint	M ²	27.00			
	3	Painting of walls plastic Paint 2 coats , and filing before painting n with all required activities:	M ²	240.00			
		GRAND TOTAL					

BOQ for Rehabilitation of Saw SHC

HF N	S/No	ACTIVITIES	Unit	Quantity	Unit Cost Af	Total Cost Af	Remarks
Saw SHC 36	1	Delivery Room Installation and supply of Floor tile 50x50 ceramic whit all respected works	M ²	22.00			
	2	Delivery Installation and supply of Wall tile 30x60 And rmoveing of wall Paint	M ²	27.00			
	3	Painting of walls plastic Paint 2 coats , and filing before painting with all required activities:	M ²	60.00			
	4	Excavation of hole for Incinerator 1.2x1.2x3.5 meter and removing of old extra materials of old hole specification with all equired activities:	M ³	7.00			
	5	Back filling of outside of hole specification with all equired activities:	M ³	5.00			
	6	Pcc concrete for (Pit) Hole m=100	M ³	1.00			
	7	RCC slabinbg thickness =10 cm concrete for pit (hole cover) with small iron door 35x35cm cover ,installation of iron pipe 3" h=1meter	piece	3.00			
	8	Plaster and filling for inside wall for (Pit) Hole M=100	M ²	100.00			
	9	Side stone masonry without Mortar specification and all required activities:	M ³	35.00			
	10	Area description for Eschew fence Installation, mast be have after every two meter an iron column D=2"inch , H=2meter reduced in PCC concrete , gage 18 and thickness 1.5 mm , the Eschew 3mm fence every one frame 1.5x2 meter mast be have around 0.75" inch Angle iron main door with weld works for related HF .	M ²	18.00			
		GRAND TOTAL					

BOQ for Rehabilitation of Alingar DH

HF N	S/No	ACTIVITIES	Unit	Quantity	Unit Cost Af	Total Cost Af	Remarks
Alingar DH 32	1	compaction and leveling of old Clay and spread one layer of low Quality plastic	M ²	120.00			
	2	PCC ccement concrete for Roof ,Gravel , local Laghman yelo send and M ; !00 1:3:6 ,Thickness = 5cm	M ²	120.00			
	3	Roofing ; Supply and Installationone layer Bituminous (Isogam) waterproofed, one Roll 40kg L= 10meter and W=1meter with all related works for roof.	M ²	130.00			
	4	Supply replacement and repiaring , installation tap, piping all related valve ,Tee , elbow, and joint based on the need and with all required activities.	LMS	5.00			
	5	Bathroom : making of new Canalizations systrem complete commode with water tank Siphon and Piping Instalation to outside mainhole with all respected works	Jop	2.00			
	6	water supply systrem , tap , hole net with all respected works	Jop	2.00			
	7	stone masonry without mortar for wall	M ³	25.00			
	8	filling of stone masonry mortar M= 1:6	M ²	100.00			
	9	making and enstallation wooden Door 0.8x2.4 meter with all respected works	piece	2.00			
	10	making and enstallation wooden window 0.7x1 meter with all respected works	piece	2.00			
	11	roof cover with wooden board plastic and clay +gutter for bathroom and pit	M ²	10.00			
		GRAND TOTAL					

BOQ for Rehabilitation of Shakhtarin

HF N	S/No	ACTIVITIES	Unit	Quantity	Unit Cost Af	Total Cost Af	Remarks
Shakhtarin SHC 31	1	Leveling of roof and spread 2 layer of plastic best Quality	M ²	100.00			
	2	straw clay (mute plaster) of roof Thickness 3.5cm , straw =1kg/meter	M ²	100.00			
	3	new Wooden Door and window wood main frame 12x7 cm and opaning part vertical , horizontally wood frame 9x4.5 cm with all respected as lock , hinge , glass hand hangar and installation, accessories and Aluminum Fly Screens	M ²	6.00			
	4	Repiaring : Wooden Door and window frame and opaning part , Repiaring with all respected as lock , hinge , glass hand hangar and installation, accessories and Aluminum Fly Screens	Piece	6.00			
		GRAND TOTAL					

BOQ for Rehabilitation of Chetela SHC

HF N	S/No	ACTIVITIES	Unit	Quantity	Unit Cost Af	Total Cost Af	Remarks
Chetela SHC 29	1	Leveling of roof and spread 2 layer of plastic best Quality	M ²	100.00			
	2	straw clay (mud plaster) of roof Thickness 3.5cm , straw =1kg/meter	M ²	100.00			
	3	Delivery Room Installation and suply of Floor tile 50x50 ceramic whith all respected works	M ²	22.00			
	4	Delivery Installation and suply of Wall tile 30x60 And rmoveing of wall Paint	M ²	27.00			
	5	painting of walls plastic Paint 2 coats , and filing before painting n with all required activities:	m2	50.00			
		GRAND TOTAL					

BOQ for Rehabilitation of Shaikh saheb CHC+

HF N	S/No	ACTIVITIES	Unit	Quantity	Unit Cost Af	Total Cost Af	Remarks
Shiaikh Saheb CHC+ 22	1	Iron sheet for ambulance : installation of iron frame 1x1.5 meter (iron Profile Thickness 1.2mm D=2.5"x1.5" Inch) with red anti oxid iron metallic 0.5mm Sheet for roof on the top of frame with respected works and installation of Gutter horizontal and vertical Iron column 3" Thickness 2.5mm	m2	20.00			
	2	replacement and repairing of outside in sid mainhole water supply system canection with main water tank , tap , hole net with all respected works	LMS Jop	4.00			
	3	painting of walls plastic Paint 2 coats , and filing before painting n with all required activities:	M ²	150.00			
		GRAND TOTAL					

BOQ for Rehabilitation of Lowkar BHC

HF N	S/No	ACTIVITIES	Unit	Quantity	Unit Cost Af	Total Cost Af	Remarks
LowKar BHC 20	1	Compaction and leveling of old Clay and spread one layer of low Quality plastic	M ²	300.00			
	2	PCC ccement concrete for Roof ,Gravel , local Laghman yelo send and M ; !00 1:3:6 ,Thickness = 5cm	M ²	300.00			
	3	Roofing ; Supply and Installationone layer Bituminous (Isogam) waterproofed, one Roll 40kg L= 10meter and W=1meter with all related works for roof.	M ²	330.00			
	4	Incinerator Repiaring and reinstalation	Piece	1.00			
	5	Wooden Door and window frame and opaning part , Repiaring with all respected as lock , hinge , glass hand hangar and installation, accessories and Aluminum Fly Screens	Piece	10.00			
		GRAND TOTAL					

BOQ for Rehabilitation of Kaho SHC

HF N	S/No	ACTIVITIES	Unit	Quantity	Unit Cost Af	Total Cost Af	Remarks
Kaho SHC 19	1	Compaction and leveling of old Clay and spread one layer of low Quality plastic	M ²	110.00			
	2	PCC ccement concrete for Roof ,Gravel , local Laghman yelo send and M ; !00 1:3:6 ,Thickness = 5cm	M ²	110.00			
	3	Roofing ; Supply and Installationone layer Bituminous (Isogam) waterproofed, one Roll 40kg L= 10meter and W=1meter with all related works for roof.	M ²	120.00			
		GRAND TOTAL					

Alokhil HF

BOQ for Rehabilitation of Alokhail BHC

HF N	S/No	ACTIVITIES	Unit	Quantity	Unit Cost Af	Total Cost Af	Remarks
Alokhail BHC 18	1	Compaction and leveling of old Clay and spread one layer of low Quality plastic	M ²	220.00			
	2	PCC ccement concrete for Roof ,Gravel , local Laghman yelo send and M ; !00 1:3:6 ,Thickness = 5cm	M ²	220.00			
	3	Roofing ; Supply and Installationone layer Bituminous (Isogam) waterproofed, one Roll 40kg L= 10meter and W=1meter with all related works for roof.	M ²	250.00			
		GRAND TOTAL					

BOQ for Rehabilitation of Salab BHC

HF N	S/No	ACTIVITIES	Unit	Quantity	Unit Cost Af	Total Cost Af	Remarks
Salab BHC 17	1	Compaction and leveling of old Clay and spread one layer of low Quality plastic	M ²	192.00			
	2	PCC ccement concrete for Roof ,Gravel , local Laghman yelo send and M ; !00 1:3:6 ,Thickness = 5cm	M ²	192.00			
	3	Roofing ; Supply and Installationone layer Bituminous (Isogam) waterproofed, one Roll 40kg L= 10meter and W=1meter with all related works for roof.	M ²	200.00			
		GRAND TOTAL					

BOQ for Rehabilitation Kachor SHC

HF N	S/No	ACTIVITIES	Unit	Quantity	Unit Cost Af	Total Cost Af	Remarks
Kachor SHC 12	1	Leveling of roof and spread 2 layer of plastic best Quality	M ²	120.00			
	2	straw clay (mutd plaster) of roof Thickness 3.5cm , straw =1kg/meter	M ²	120.00			
		GRAND TOTAL					

BOQ for Rehabilitation of Kulman

HF N	S/No	ACTIVITIES	Unit	Quantity	Unit Cost Af	Total Cost Af	Remarks
Kulman PHC 11	1	Leveling of roof and spread 2 layer of plastic best Quality	M ²	120.00			
	2	straw clay (mute plaster) of roof Thickness 3.5cm , straw =1kg/meter	M ²	120.00			
	3	Making and enstallation wooden partition wall with opening part for window frame size 6x6cm and board 1" Wood of kunar with all respected works	M ²	18.00			
		GRAND TOTAL					

BOQ for Rehabilitation of Sangar BHC

HF N	S/No	ACTIVITIES	Unit	Quantity	Unit Cost Af	Total Cost Af	Remarks
Sangar BHC 10	1	Making and enstallation wooden partition wall with opening part for window frame size 6x6cm and board 1" Wood of kunar with all respected works	M ²	18.00			
	2	Supply replacement and installation water tap, piping all related valve ,Tee , elbow, and joint based on the need and with all required activities.	LMS	2.00			
		GRAND TOTAL					