

## BOQ for Rehabilitation of Charbagh CHC

HF N	S/No	ACTIVITIES	Unit	Quantity	Unit Cost Af	Total Cost Af	Remarks
Charbagh CHC 1	1	Compaction and leveling of old Clay and spread one layer of low Quality plastic	M <sup>2</sup>	110.00			
	2	PCC ccement concrete for Roof ,Gravel , local Laghman yelo send and M ; !00 1:3:6 ,Thickness = 4cm	M <sup>2</sup>	60.00			
	3	Roofing ; Supply and Installationone layer Bituminous (Isogam) waterproofed, one Roll 40kg L= 10meter and W=1meter with all related works for roof.	M <sup>2</sup>	115.00			
	4	Supply and installation of best Quality 1000 liter plastic water tank with with all required activities:	piece	1.00			
	5	Replacement of tap , mixer, and extra pipe for sink and water tank of commode with all required activities:	set	10.00			
		<b>GRAND TOTAL</b>					

## BOQ for Rehabilitation Omarzai SHC

HF N	S/No	ACTIVITIES	Unit	Quantity	Unit Cost Af	Total Cost Af	Remarks
Omarzai SHC 2	1	Delivery Room Installation and supply of Floor tile 50x50 ceramic whit all respected works	M <sup>2</sup>	23.00			
	2	Delivery Installation and supply of Wall tile 30x60 And rmoveing of wall Paint	M <sup>2</sup>	25.00			
	3	Supply replacement and rpiaring of canalization and water supply system installation water tap, piping all related valve ,Tee , elbow, and joint based on the need and with all required activities.	LMS/Jop	3.00			building indoor and outdoor canalization
	4	Pit : Excavation of hole for Incinerator 1.2x1.2x3.5 meter and with all equired activities:	M <sup>3</sup>	7.00			
	5	back filling of outside of hole specification with all equired activities:	M <sup>3</sup>	5.00			
	6	Pcc concrete for (Pit) Hole m=100	M <sup>3</sup>	1.00			
	7	RCC slabinbg thickness =10 cm concrete for pit (hole cover ) with small iron door 35x35cm cover with all required activities.,	piece	3.00			
	8	plaster and filling for inside wall for (Pit) Hole M=100	M <sup>2</sup>	100.00			
	9	stone masonry without Mortar specification and all required activities:	M <sup>3</sup>	35.00			

	10	Area description for Eschew fence Installation, mast be have after every two meter an iron column D=2"inch , H=2meter reduced in PCC concrete , gage 18 and thickness 1.5 mm , the Eschew 3mm fence every one frame 1.5x2 meter mast be have around 0.75" inch Angle iron main door with weld works for related HF .	M <sup>2</sup>	18.00			this includes waste pits and fence construction
		GRAND TOTAL					

## BOQ for Rehabilitation Chapa darya SHC

HF N	S/No	ACTIVITIES	Unit	Quantity	Unit Cost Af	Total Cost Af	Remarks
Chapa Drya SHC 4	1	Compaction and leveling of old Clay and spread one layer of high Quality plastic	M <sup>2</sup>	120.00			
	2	Straw clay (mud plaster ) of roof Thickness 3.5cm , straw =1kg/meter	M <sup>2</sup>	120.00			
		GRAND TOTAL					

## BOQ for Rehabilitation of Katal BHC

HF N	S/No	ACTIVITIES	Unit	Quantity	Unit Cost Af	Total Cost Af	Remarks
Katal BHC 8	1	making and enstallation wooden window 0.7x1 meter with all respected works	piece	2.00			
	2	for Wooden window & Door replicement and repiaring of all respected as lock , hinge , glass hand hangar and installation, accessories and Aluminum Fly Screens	piece	8.00			
	3	roof cover with wooden board plastic and clay +gutter for bathroom and pit	M <sup>2</sup>	20.00			
	4	Supply replacement and installation water tap, piping all related valve ,Tee , elbow, and joint based on the need and with all required activities.	set	2.00			
		<b>GRAND TOTAL</b>					

## BOQ for Rehabilitation of Mehtarlam CHC

HF N	S/No	ACTIVITIES	Unit	Quantity	Unit Cost Af	Total Cost Af	Remarks
Mehtarlam CHC 15	1	some bathroom replacement and Installation and suply of Floor tile ceramic whith all respected works	M <sup>2</sup>	18.00			
	2	PCC : Vaccine Room and new bathroom PCC With M150 for room and wak way and all required activities	M <sup>3</sup>	3.00			
	3	Supply replacement and installation water tap, piping all related valve ,Tee , elbow, and joint based on the need ,outside main hand hole and with all required activities.	LMS	3.00			
		GRAND TOTAL					

## BOQ for Rehabilitation Dewa BHC

HF N	S/No	ACTIVITIES	Unit	Quantity	Unit Cost Af	Total Cost Af	Remarks
Dewa BHC 16	1	Delivery Room Installation and supply of Floor tile 50x50 ceramic whit all respected works	M <sup>2</sup>	22.00			
	2	Delivery Installation and supply of Wall tile 30x60 And rmoveing of wall Paint	M <sup>2</sup>	27.00			
	3	Supply and installation of,6socket , 6 holder , 6 light 24w , swatch , one fuse with all wiring and with all required activities.	LMS job	2.00			
	4	compaction and leveling of old Clay and spread one layer of low Qualty plastic	M <sup>2</sup>	180.00			
	5	PCC ccement concrete for Roof ,Gravel , local Laghman yellow send and M ; !00 1:3:6 ,Thickness = 5cm	M <sup>2</sup>	180.00			
	6	Roofing ; Supply and Installationone layer Bituminous (Isogam) waterproofed, one Roll 40kg L= 10meter and W=1meter with all related works for roof.	M <sup>2</sup>	190.00			
		<b>GRAND TOTAL</b>					

## BOQ for Rehabilitation of Kashmond BHC

HF N	S/No	ACTIVITIES	Unit	Quantity	Unit Cost Af	Total Cost Af	Remarks
Kashmond BHC 23	1	Compaction and leveling of old Clay and spread one layer of low Quality plastic	M <sup>2</sup>	150.00			
	2	PCC ccement concrete for Roof ,Gravel , local Laghman yelo send and M ; !00 1:3:6 ,Thickness = 5cm	M <sup>2</sup>	150.00			
	3	Roofing ; Supply and Installationone layer Bituminous (Isogam) waterproofed, one Roll 40kg L= 10meter and W=1meter with all related works for roof.	M <sup>2</sup>	160.00			
		GRAND TOTAL					



## BOQ for Rehabilitation of Aziz khan Kas BHC

HF N	S/No	ACTIVITIES	Unit	Quantity	Unit Cost Af	Total Cost Af	Remarks
Azizkhan kas BHC 26	1	Compaction and leveling of old Clay and spread one layer of low Quality plastic	M <sup>2</sup>	100.00			
	2	PCC ccement concrete for Roof ,Gravel , local Laghman yelo send and M ; !00 1:3:6 ,Thickness = 5cm	M <sup>2</sup>	100.00			
	3	Roofing ; Supply and Installationone layer Bituminous (Isogam) waterproofed, one Roll 40kg L= 10meter and W=1meter with all related works for roof.	M <sup>2</sup>	100.00			
	4	Making of new main hand hole inastallation of cover 40x40	piece	8.00			
	5	Repairing and Replacement of tap ,mixet , extrapipe , net of hole and shower with all respected works	LMS Jop	4.00			
	6	Making of new Canalizations and water supply system complete bisan ( sink) Siphon and Piping jointe to outside mainhole with all respected works	Jop	1.00			
		<b>GRAND TOTAL</b>					

## BOQ for Rehabilitation of Zafaran SHC

HF N	S/No	ACTIVITIES	Unit	Quantity	Unit Cost Af	Total Cost Af	Remarks
Zafaran SHC 27	1	Leveling of roof and spread 2 layer of plastic best Quality	M <sup>2</sup>	280.00			
	2	straw clay (mud plaster ) of roof Thickness 3.5cm , straw =1kg/meter	M <sup>2</sup>	280.00			
	3	Installation precast slab 05x100 cm for parapet with all related works for roof.	piece	70.00			
		GRAND TOTAL					

## BOQ for Rehabilitation of Qarghayee CHC

HF N	S/No	ACTIVITIES	Unit	Quantity	Unit Cost Af	Total Cost Af	Remarks
Qarghayee CHC 28	1	Compaction and leveling of old Clay and spread one layer of low Quality plastic	M <sup>2</sup>	100.00			
	2	PCC cement concrete for Roof ,Gravel , local Laghman yelo send and M ; 100 1:3:6 ,Thickness = 4cm	M <sup>2</sup>	100.00			
	3	Roofing ; Supply and Installation one layer Bituminous (Isogam) waterproofed, one Roll 40kg L= 10meter and W=1meter with all related works for roof.	M <sup>2</sup>	400.00			
	4	Plastering for wall inside outside (M=1:6) and based on the design, and specification with all required activities:	m2	100.00			
	5	<b>Repiaring</b> : Wooden Door and window frame and opening part , Repiaring with all respected as lock , hinge , glass hand hangar and installation, accessories and Aluminum Fly Screens	Piece	10.00			
		<b>GRAND TOTAL</b>					

## BOQ for Rehabilitation of Ghondi SHC

HF N	S/No	ACTIVITIES	Unit	Quantity	Unit Cost Af	Total Cost Af	Remarks
Ghondi SHC	1	Making of new main hand hole inastallation of cover 40x40	piece	6.00			
	2	Area description for Eschew fence Installation, mast be have after every two meter an iron column D=2"inch , H=2meter reduced in PCC concrete , gage 18 and thickness 1.5 mm , the Eschew 3mm fence every one frame 1.5x2 meter mast be have around 0.75" inch Angle iron main door with weld works for related HF .	M <sup>2</sup>	20.00			
		GRAND TOTAL					

## BOQ for Rehabilitation of kanda BHC

HF N	S/No	ACTIVITIES	Unit	Quantity	Unit Cost Af	Total Cost Af	Remarks
Kanda BHC 33	1	RCC slabinbg thickness =10 cm concrete for pit (hole cover ) with small iron door 35x35cm cover	M2	3.00			
	2	<b>Repiaring</b> : Wooden Door and window frame and opaning part , Repiaring with all respected as lock , hinge , glass hand hangar and installation, accessories and Aluminum Fly Screens	Piece	8.00			
	3	Supply replacement and repiaring , installation tap, piping all related valve ,Tee , elbow, and joint based on the need and with all required activities.	LMS	6.00			
	4	PCC : PCC With M150 for room and wak way and all required activities	M <sup>3</sup>	3.50			
		<b>GRAND TOTAL</b>					

## BOQ for Rehabilitation of Karanch SHC

HF N	S/No	ACTIVITIES	Unit	Quantity	Unit Cost Af	Total Cost Af	Remarks
Karanch SHC 34	1	RCC slabinbg thickness =10 cm concrete for pit (hole cover ) with small iron door 35x35cm cover ,installation of iron pipe 3" h=1meter	m2	6.00			
	2	Supply replacement and repiaring , installation tap, piping all related valve ,Tee , elbow, and joint based on the need and with all required activities.	LMS	3.00			
		GRAND TOTAL					

## BOQ for Rehabilitation of Gularam SHC

HF N	S/No	ACTIVITIES	Unit	Quantity	Unit Cost Af	Total Cost Af	Remarks
Gularam SHC 35	1	Delivery Room Installation and suply of Floor tile 50x50 ceramic whith all respected works	M <sup>2</sup>	27.00			
	2	Delivery Installation and suply of Wall tile 30x60 And rmoveing of wall Paint	M <sup>2</sup>	30.00			
	3	One room repairing ( plaster , painting ,tiling and water sapply system )	LMS	1.00			
		GRAND TOTAL					

BOQ for Rehabilitation of Shamati BHC

HF N	S/No	ACTIVITIES	Unit	Quantity	Unit Cost Af	Total Cost Af	Remarks
Shamati BHC 38	1	Repiaring : painting ,plastering and small rehabilitatioin for floor for bathroom	LMS	2.00			
		GRAND TOTAL					



## BOQ for Rehabilitation of Zirani SHC

HF N	S/No	ACTIVITIES	Unit	Quantity	Unit Cost Af	Total Cost Af	Remarks
Zirani SHC 39	1	Making of new canalization system piping pipe 5" and joint with min hole and side mast be cover with bricks and plaster	meter	20.00			
	2	Making of new main hand hole inastallation of cover 40x40	piece	5.00			
		GRAND TOTAL					

## BOQ for Rehabilitation of Alishing BHC

HF N	S/No	ACTIVITIES	Unit	Quantity	Unit Cost Af	Total Cost Af	Remarks
Alishing BHC 40	1	Compaction and leveling of old Clay and spread one layer of low Quality plastic	M <sup>2</sup>	240.00			
	2	PCC ccement concrete for Roof ,Gravel , local Laghman yelo send and M ; !00 1:3:6 ,Thickness = 3cm	M <sup>2</sup>	240.00			
	3	Roofing ; Supply and Installationone layer Bituminous (Isogam) waterproofed, one Roll 40kg L= 10meter and W=1meter with all related works for roof.	M <sup>2</sup>	300.00			
	4	Repairing and Replacement of Canalizations systrem Outsidi insid Siphon and Piping Instalation to outside mainhole with all respected works	LMS Jop	3.00			
	5	Removing and Reinstalation of old main iron Door with all brick masonry and welding works	piece	1.00			
		<b>GRAND TOTAL</b>					

## BOQ for Rehabilitation of Surkhakan CHC

HF N	S/No	ACTIVITIES	Unit	Quantity	Unit Cost Af	Total Cost Af	Remarks
Surkhakan CHC 41	1	Supply and installation of energy sewer light 40 W	piece	30.00			
	2	Supply installation of holder 40 W	piece	30.00			
	3	Supply replacement of water filter with installation water tap, piping all related valve ,Tee , elbow, and joint based on the need ,outside main hand hole and with all required activities.	jop	2.00			
	4	Supply replacement of PVC pipe 5", outside main hand hole repiarin , with all required activities.	meter	5.00			
	5	<b>Iron sheet</b> : installation Profile Thickness <b>1.2mm D=3"x1.5" Inch</b> ) and replcement of iron metallic 0.5mm Sheet for roof on the top of frame with respected works	m2	6.00			
	6	Plastic and oil paint with all required activities:	m2	40.00			
		<b>GRAND TOTAL</b>					