



## Delivery Location: Zinda Jan District Targeted Villages

#	Items Description	QTY	UoM	Unit Cost AFN	Total Cost AFN	Remark
1	<p>High quality Stone (Stright Shaped at least on the both sides, Hard, Well Shaped, and sized, crashed, Free from cavities, cracks, or patches and without soft or loose materials) should be between 15 to 35 cm in size and sourced from the Gazargah or shaidai areas . the stone will be measured and calculated based on cubic meters of work , including transportation costs to all project sites. it is mentionable that the items will be transported to 4 villages in Zandajan district which the distance is 50-70 KM far away from Herat city.</p> <p>Vendors might assure the quality of all provided items, otherwise if the items are rejected by technical team replacing cost responsibilities are with vendors. Cost of All types of tests for Stone requested by the technical engineer might be included in the quotation.</p> <p>سنگ با کیفیت با ابعاد 15 الی 35 سانتی متری باید باشد و از منابع گازرگاه یا شیدای تهیه شود همچنان برمنای مرمکعب کار شده محاسبه خواهد گردید. همراهی هزینه حمل و نقل به تمام پروژه ها در نظر گرفته شود ، قابل ذکر است که این قلم به قریه ولسوالی زندجان که فاصله آنها از شهر هرات 50 تا 70 کیلومتر است، انتقال می یابند. سربکست ها باید بیت تمام اقلام ارایه شده را تضمین کنند در صورت رد شدن اقلام توسط تیم تخنیکي هزینه جایگزین به مسولیت سربکست ها است و هزینه تست های که از طرف تیم تخنیکي تعین میشود به عهده سربکست می باشد. نوبت پروژه ها در دامنه ها و دره ها و رودخانه ها است سربکست نرخ دهنده در قسمت هزینه انتقال این مورد را در نظر بگیرد</p>	1170	m3		0	
2	<p>Gabion Box (Double twisted mesh wire diameter is 3mm, hexagonal mesh opening is 100mmX120mm, Servedge wire diameter is 4 mm, Lacing Wire diameter is 2.2 mm, surface treatment is heavily hot dip galvanized (zinc coating=300-320g/square meter). One set includes gabion mesh, diaphragm, and lacing wire.</p> <p>Gabion Box Size will be in different sizes (100cmX100cmX100cm, 150cmX100cmX100cm 200cmX100cmX100cm and 250cmX100cmX100cm) and the amount will be clarified to the vendor by technical team according to the field need. Note: The cost of gabions, the cost of gabion weaving, the cost of waste in gabion weaving, and all transportation costs of the woven gabion boxes to the relevant projects must be considered. It should be noted that these items will be transported to the projects in the Zinda Jan district in 4 different villages which the distance is 50 to 70 km far away from Herat city villages,</p> <p>Vendors might assure the quality of all provided items, otherwise if the items are rejected by technical team replacing cost responsibilities are with vendors. Cost of All types of tests for wire of gabion requested by the technical engineer might be included in the quotation.</p> <p>جعبه های گابیون بافته شده با استفاده از سیم مش دویل تابیده به قطر 3 میلی متری و سیم لبه با فرم یا قطر 4 میلی متری و با ابعاد فاصله مش. شش ضلعی 100 میلی متری x 120 میلی متری. های گابیون به کار رفته در این جعبه ها باید از نوع گالوانیزه گرم سنگین با قطر 3 میلی متری و بهیلهی مری بوده و روکش گالوانیزه آن ها باید به 300 الی 320 گرم در هر متر مربع جست داشته باشند. مجموعه شامل مش گابیون، دیافراگم و بافت گابیون می باشد. جعبه های گابیون باید در اندازه های مختلف بافته شوند که بر اساس نیاز پروژه ها توسط تیم تخنیکي به سربکست قراردادی اندازه ها داده می شود. نوبت هزینه سیم گابیون ها باجست بالا 300 گرم بر متر مربع ، هزینه بافت سیم گابیون، هزینه ضایعات سیم گابیون در بافت و تمام هزینه های حمل و نقل جعبه های بافته شده گابیون به پروژه های مربوطه باید در نظر گرفته شود. شلایم به ذکر است که این اقلام به پروژه های ولسوالی زنده جان و بقویه های مختلف که فاصله آن ها از مرکز شهر هرات 50 تا 70 کیلومتر است منتقل خواهد شد و هزینه تست های از طرف تیم تخنیکي تعین میشود به عهده سربکست می باشد. نوبت پروژه ها در دامنه ها و دره ها و رودخانه ها است سربکست نرخ دهنده در قسمت هزینه انتقال این مورد را در نظر بگیرد</p>	17000	Kg		0	
3	<p>Lacing Wire diameter is 2.2 mm, surface treatment is heavily hot dip galvanized (zinc coating=300- 320g/square meter).</p> <p>Note: The cost of gabions and all transportation costs of the wire of gabion to the relevant projects must be considered. It should be noted that these items will be transported to the projects in the Zinda Jan district in 4 different villages which the distance is 50 to 70 km far away from Herat city villages,</p> <p>Vendors might assure the quality of all provided items, otherwise if the items are rejected by technical team replacing cost responsibilities are with vendors. Cost of All types of tests for Wire of Gaboin requested by the technical engineer might be included in the quotation.</p> <p>سیم گره زنی یا بسته بندی جعبه های گابیون با قطر 2 میلی متری و پوشش سطحی جسی. گالوانیزه گرم سنگین به میزان 300-320 گرم بر متر مربع. نوبت هزینه سیم گابیون ها باجست بالا 300 گرم بر متر مربع ، و تمام هزینه های حمل و نقل گابیون به پروژه های مربوطه باید در نظر گرفته شود. لازم به ذکر است که این اقلام به پروژه های ولسوالی زنده جان و بقویه های مختلف که فاصله آن ها از مرکز شهر هرات 50 تا 70 کیلومتر است، منتقل خواهد شد و هزینه تست های که از طرف تیم تخنیکي تعین میشود به عهده سربکست می باشد</p>	380	Kg		0	
Total Cost in AFN					0	